

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

44000500	COMBINATION CURB & GUTTER REMOVAL		REMARKS	
	FOOT	LOCATION		
		<i>Ramps</i>		
	83	Sta. 23 + 28 to 24 + 04	LT	
	80	Sta. 30 + 33 to 30 + 95	LT	
	81	Sta. 66 + 51 to 67 + 27	LT	
	81	Sta. 80 + 33 to 80 + 94	LT	
TOTAL	325			

44003100	MEDIAN REMOVAL		REMARKS	
	SQ FT	LOCATION		
		<i>IL 72</i>		
	12745	Sta. 21915 + 59 to 21926 + 54	Median	
	19742	Sta. 21927 + 50 to 21940 + 27	Median	
	10415	Sta. 21940 + 77 to 21948 + 59	Median	
		<i>Ramps</i>		
	281	Sta. 23 + 88 to 24 + 06	Island	
	292	Sta. 67 + 11 to 67 + 28	Island	
TOTAL	43475			

44004000	PAVED DITCH REMOVAL		REMARKS	
	FOOT	LOCATION		
		<i>IL 72</i>		
	234	Sta. 21932 + 14 to 21934 + 48	LT	
	222	Sta. 21932 + 22 to 21934 + 44	RT	
TOTAL	456			

44004250	PAVED SHOULDER REMOVAL		REMARKS	
	SQ YD	LOCATION		
		<i>IL 72</i>		
	1136	Sta. 21928 + 50 to 21938 + 50	LT	
	1142	Sta. 21928 + 50 to 21938 + 50	RT	
		<i>Ramps</i>		
	134	Sta. 23 + 30 to 24 + 14	RT	
	19	Sta. 30 + 97 to 31 + 36	LT	
	132	Sta. 66 + 48 to 67 + 37	RT	
	17	Sta. 80 + 96 to 81 + 62	LT	
	171	Sta. 80 + 23 to 81 + 62	RT	
TOTAL	2752			

50104400	CONCRETE HEADWALL REMOVAL		REMARKS	
	EACH	LOCATION		
		<i>IL 72</i>		
	1	Sta. 21924 + 71	RT	
TOTAL	1			

542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"		REMARKS	
	FOOT	LOCATION		
		<i>IL 72</i>		
	40	Sta. 21914 + 50	RT	
TOTAL	40			

542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"		REMARKS	
	FOOT	LOCATION		
		<i>IL 72</i>		
	46	Sta. 21948 + 70	RT	
TOTAL	46			

54213450	END SECTIONS 15"		REMARKS	
	EACH	LOCATION		
		<i>IL 72</i>		
	2	Sta. 21914 + 50	RT	
TOTAL	2			

54213453	END SECTIONS 18"		REMARKS	
	EACH	LOCATION		
		<i>IL 72</i>		
	2	Sta. 21948 + 70	RT	
TOTAL	2			

550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"		REMARKS	
	FOOT	LOCATION		
		<i>IL 72</i>		
	6	Sta. 21927 + 30	RT	
	6	Sta. 21941 + 05	RT	
TOTAL	12			

60100060	CONCRETE HEADWALL FOR PIPE DRAINS		REMARKS	
	EACH	LOCATION		
		<i>IL 72</i>		
	1	Sta. 21914 + 00	LT	
	1	Sta. 21914 + 00	RT	
	1	Sta. 21915 + 75	LT	
	1	Sta. 21915 + 75	RT	
	1	Sta. 21917 + 50	LT	
	1	Sta. 21917 + 50	RT	
	1	Sta. 21920 + 00	LT	
	1	Sta. 21920 + 00	RT	
	1	Sta. 21922 + 50	LT	
	1	Sta. 21922 + 50	RT	
	1	Sta. 21925 + 00	RT	
	1	Sta. 21926 + 85	RT	
	1	Sta. 21928 + 50	LT	
	1	Sta. 21928 + 50	RT	
	1	Sta. 21930 + 25	LT	
	1	Sta. 21930 + 25	RT	
	1	Sta. 21932 + 00	LT	
	1	Sta. 21932 + 00	RT	
	1	Sta. 21935 + 00	LT	
	1	Sta. 21935 + 00	RT	
	1	Sta. 21936 + 85	LT	
	1	Sta. 21936 + 85	RT	
	1	Sta. 21938 + 50	RT	
	1	Sta. 21940 + 25	RT	
	1	Sta. 21942 + 00	LT	
	1	Sta. 21942 + 00	RT	
	1	Sta. 21944 + 35	LT	
	1	Sta. 21944 + 35	RT	
	1	Sta. 21946 + 85	LT	
	1	Sta. 21946 + 85	RT	
		<i>Ramps</i>		
	1	Sta. 23 + 30	RT	
	1	Sta. 31 + 61	RT	
	1	Sta. 66 + 48	RT	
	1	Sta. 81 + 62	RT	
TOTAL	34			

PLOT DATE = Mon Mar 28 14:08:27 2005
 PLOT NAME = c:\projects\120RS-3\120RS-3.dwg
 PLOT SCALE = 1/16" = 1' / IN.
 USER NAME = jlljgk