

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID				REMARKS
EACH	LOCATION				
	<i>IL 72</i>				
1	Sta.	21917 + 57			Median
1	Sta.	21920 + 58			Median
1	Sta.	21931 + 06			Median
1	Sta.	21935 + 06			Median
1	Sta.	21944 + 08			Median
<b>TOTAL</b>	<b>5</b>				

60500060	REMOVING INLETS				REMARKS
EACH	LOCATION				
	<i>IL 72</i>				
1	Sta.	21927 + 24			Median
1	Sta.	21940 + 98			Median
<b>TOTAL</b>	<b>2</b>				

60600095	CLASS SI CONCRETE (OUTLET)				REMARKS
CU YD	LOCATION				
	<i>Ramps</i>				
1.23	Sta.	23 + 30	to	23 + 42	RT
1.23	Sta.	30 + 86	to	30 + 98	LT
1.23	Sta.	66 + 65	to	66 + 77	RT
1.23	Sta.	80 + 86	to	80 + 98	LT
<b>TOTAL</b>	<b>4.92</b>				

60608600	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.06				REMARKS
FOOT	LOCATION				
	<i>IL 72</i>				
572.5	Sta.	21916 + 93	to	21922 + 64.5	LT
574	Sta.	21916 + 93	to	21922 + 64.5	RT
909	Sta.	21927 + 25	to	21936 + 34	LT
911	Sta.	21927 + 25	to	21936 + 34	RT
567	Sta.	21940 + 97	to	21946 + 64	LT
569	Sta.	21940 + 97	to	21946 + 64	RT
<b>TOTAL</b>	<b>4102.5</b>				

60610400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24				REMARKS
FOOT	LOCATION				
	<i>Ramps</i>				
68	Sta.	23 + 42	to	24 + 05	LT
67	Sta.	30 + 33	to	30 + 86	LT
68	Sta.	66 + 65	to	67 + 28	LT
67	Sta.	80 + 33	to	80 + 86	LT
<b>TOTAL</b>	<b>270</b>				

60614600	PAVED DITCH (SPECIAL)				REMARKS
FOOT	LOCATION				
	<i>IL 72</i>				
20	Sta.	21932 + 16	to	21932 + 36	LT
20	Sta.	21932 + 20	to	21932 + 38	RT
212	Sta.	21932 + 36	to	21934 + 48	LT
206	Sta.	21932 + 38	to	21934 + 44	RT
<b>TOTAL</b>	<b>458</b>				

60618300	CONCRETE MEDIAN SURFACE, 4 INCH				REMARKS
SQ FT	LOCATION				
	<i>IL 72</i>				
7176	Sta.	21917 + 14	to	21922 + 65	Median
14014	Sta.	21927 + 25	to	21936 + 34	Median
6828	Sta.	21940 + 97	to	21946 + 64	Median
307	Sta.	23 + 88	to	24 + 06	Island
296	Sta.	67 + 11	to	67 + 28	Island
<b>TOTAL</b>	<b>28621</b>				

60622400	CONCRETE MEDIAN, TYPE SM-6.06				REMARKS
SQ FT	LOCATION				
	<i>IL 72</i>				
39	Sta.	21916 + 86	to	21916 + 93	Median
2966	Sta.	21922 + 64.5	to	21926 + 44.5	Median
52	Sta.	21927 + 17	to	21927 + 25	Median
3049	Sta.	21936 + 34	to	21940 + 17	Median
52	Sta.	21940 + 89	to	21940 + 97	Median
19	Sta.	21946 + 64	to	21946 + 69	Median
<b>TOTAL</b>	<b>6177</b>				

60624600	CORRUGATED MEDIAN				REMARKS
SQ FT	LOCATION				
	<i>IL 72</i>				
938	Sta.	21915 + 59	to	21917 + 72	Median
831	Sta.	21945 + 86	to	21948 + 00	Median
<b>TOTAL</b>	<b>1769</b>				

66700305	PERMANENT SURVEY MARKERS, TYPE II				REMARKS
EACH	LOCATION				
	<i>IL 72</i>				
1	Sta.	21924 + 30		60' RT	FE
1	Sta.	21948 + 55		40' RT	FE
<b>TOTAL</b>	<b>2</b>				

78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS				REMARKS
SQ FT	LOCATION				
	<i>White</i>				
15.6	Sta.	21924 + 22			LT Turn Arrow
15.6	Sta.	21924 + 89			LT Turn Arrow
15.6	Sta.	21925 + 56			LT Turn Arrow
15.6	Sta.	21926 + 24			LT Turn Arrow
15.6	Sta.	21937 + 93			LT Turn Arrow
15.6	Sta.	21938 + 63			LT Turn Arrow
15.6	Sta.	21939 + 30			LT Turn Arrow
15.6	Sta.	21939 + 95			LT Turn Arrow
<b>TOTAL</b>	<b>124.8</b>				

78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"				REMARKS
FOOT	LOCATION				
	<i>White</i>				
140	Sta.	21912 + 88	to	21914 + 28	EB EOP
3507	Sta.	21914 + 28	to	21949 + 35	EB EOP
140	Sta.	21949 + 35	to	21950 + 75	EB EOP
140	Sta.	21912 + 88	to	21914 + 28	WB EOP
3507	Sta.	21914 + 28	to	21949 + 35	WB EOP
140	Sta.	21949 + 35	to	21950 + 75	WB EOP
	<i>Limestone Rd</i>				
195	Sta.	90 + 13	to	90 + 75	LT & RT EOP
<b>Sub-Total</b>	<b>7769</b>				

	<i>White</i>				REMARKS
	<i>Ramps</i>				
285	Sta.	22 + 30	to	24 + 15	EOP
315	Sta.	30 + 23	to	32 + 62	EOP
285	Sta.	65 + 49	to	67 + 38	EOP
315	Sta.	80 + 23	to	82 + 63	EOP
<b>Sub-Total</b>	<b>1200</b>				

	<i>Yellow</i>				REMARKS
	<i>Ramps</i>				
200	Sta.	22 + 30	to	24 + 07	EOP
240	Sta.	30 + 30	to	32 + 62	EOP
200	Sta.	65 + 49	to	67 + 30	EOP
240	Sta.	80 + 31	to	82 + 63	EOP
<b>Sub-Total</b>	<b>880</b>				

	<i>Yellow</i>				REMARKS
	<i>IL 72</i>				
35	Sta.	21912 + 88	to	21914 + 28	CL Dash
300	Sta.	21914 + 28	to	21915 + 59	DY
1086	Sta.	21915 + 59	to	21926 + 45	SY WB
1086	Sta.	21915 + 59	to	21926 + 45	SY EB
1301	Sta.	21927 + 16	to	21940 + 17	SY WB
1301	Sta.	21927 + 16	to	21940 + 17	SY EB
711	Sta.	21940 + 89	to	21948 + 00	SY WB
711	Sta.	21940 + 89	to	21948 + 00	SY EB
270	Sta.	21948 + 00	to	21949 + 35	DY
35	Sta.	21949 + 35	to	21950 + 75	CL Dash
	<i>Limestone Rd</i>				
30	Sta.	90 + 13	to	90 + 75	CL Dash
<b>Sub-Total</b>	<b>6866</b>				
<b>TOTAL</b>	<b>16715</b>				

78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"				REMARKS
FOOT	LOCATION				
	<i>White</i>				
240	Sta.	21924 + 04	to	21926 + 44	Turn Lane
240	Sta.	21937 + 77	to	21940 + 17	Turn Lane
<b>Sub-Total</b>	<b>480</b>				

	<i>White</i>				REMARKS
	<i>Ramps</i>				
184	Sta.	23 + 71	to	24 + 14	Island
184	Sta.	66 + 95	to	67 + 38	Island
<b>Sub-Total</b>	<b>368</b>				
<b>TOTAL</b>	<b>848</b>				

78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"				REMARKS
FOOT	LOCATION				
	<i>White</i>				
162	Sta.	23 + 71	to	24 + 14	Island
161	Sta.	66 + 95	to	67 + 38	Island
<b>TOTAL</b>	<b>323</b>				

PLOT DATE = Mon Mar 28 14:58:38 2005  
 PLOT NAME = G:\p\m\m\21826\c15206\ch.dgn  
 PLOT SCALE = 1/8" = 1' / IN  
 USER NAME = jlljg