

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"				REMARKS
	FOOT	LOCATION			
	<i>White</i>				
	<i>Ramps</i>				
	18	Sta.	23 + 85	LT	Stop Bar
	18	Sta.	23 + 93	RT	Stop Bar
	18	Sta.	67 + 12	LT	Stop Bar
	18	Sta.	67 + 15	RT	Stop Bar
	<i>Limestone Rd.</i>				
	29	Sta.	90 + 45	LT	Stop Bar
TOTAL	101				

78100100	RAISED REFLECTIVE PAVEMENT MARKER				REMARKS
	EACH	LOCATION			
	<i>Two-Way Amber</i>				
	<i>IL 72</i>				
	2	Sta.	21912 + 88	to 21914 + 28	1 @ 80' o.c.
	8	Sta.	21914 + 28	to 21915 + 59	2 @ 40' o.c.
	8	Sta.	21948 + 00	to 21949 + 35	2 @ 40' o.c.
	2	Sta.	21949 + 35	to 21950 + 75	1 @ 80' o.c.
Sub-Total	20				
	<i>One-Way Amber</i>				
	<i>IL 72</i>				
	54	Sta.	21915 + 59	to 21926 + 45	2 @ 40' o.c.
	66	Sta.	21927 + 16	to 21940 + 17	2 @ 40' o.c.
	36	Sta.	21940 + 89	to 21948 + 00	2 @ 40' o.c.
Sub-Total	156				
	<i>One-Way White</i>				
	<i>IL 72</i>				
	7	Sta.	21924 + 05	to 21926 + 45	1 @ 40' o.c.
	7	Sta.	21937 + 77	to 21940 + 17	1 @ 40' o.c.
Sub-Total	14				
TOTAL	190				

78300100	PAVEMENT MARKING REMOVAL				REMARKS
	SQ FT	LOCATION			
	<i>IL 72</i>				
	Entire Length of Job. Edge Lines and Center Line. For Staging				
TOTAL	5843				

78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				REMARKS
	EACH	LOCATION			
	<i>IL 72</i>				
	3	Sta.	21912 + 88	to 21914 + 28	
	3	Sta.	21949 + 35	to 21950 + 75	
TOTAL	6				

X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL				REMARKS
	EACH	LOCATION			
	<i>IL 72</i>				
	1	Sta.	21918 + 05	LT	
	1	Sta.	21921 + 03	RT	
	1	Sta.	21923 + 27	RT	
	1	Sta.	21925 + 11	LT	
	1	Sta.	21935 + 52	RT	
	1	Sta.	21938 + 31	LT	
TOTAL	6				

X0712400	TEMPORARY PAVEMENT				REMARKS
	SQ YD	LOCATION			
	<i>IL 72</i>				
	44	Sta.	21925 + 74	to 21926 + 53	
	133	Sta.	21927 + 05	to 21928 + 11	
	46	Sta.	21939 + 47	to 21940 + 27	
	135	Sta.	21940 + 77	to 21941 + 83	
	<i>Ramps</i>				
	77	Sta.	23 + 40	to 23 + 97	
	31	Sta.	23 + 88	to 24 + 06	
	76	Sta.	66 + 62	to 67 + 19	
	32.0	Sta.	67 + 11	to 67 + 28	
TOTAL	574				

X6064201	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.06				REMARKS
	FOOT	LOCATION			
	<i>Ramps</i>				
	94	Sta.	23 + 88	to 24 + 06	Island
	92	Sta.	67 + 11	to 67 + 28	Island
TOTAL	186				

XX146400	STORM SEWER REMOVAL				REMARKS
	FOOT	LOCATION			
	<i>IL 72</i>				
	10	Sta.	21940 + 98	RT	
	10	Sta.	21927 + 24	RT	
TOTAL	20				

Z0040530	PIPE UNDERDRAIN REMOVAL				REMARKS
	FOOT	LOCATION			
	<i>IL 72</i>				
	175	Sta.	21914 + 00	to 21915 + 75	LT
	175	Sta.	21914 + 00	to 21915 + 75	RT
	175	Sta.	21915 + 75	to 21917 + 50	LT
	175	Sta.	21915 + 75	to 21917 + 50	RT
	250	Sta.	21917 + 50	to 21920 + 00	LT
	250	Sta.	21917 + 50	to 21920 + 00	RT
	250	Sta.	21920 + 00	to 21922 + 50	LT
	250	Sta.	21920 + 00	to 21922 + 50	RT
	250	Sta.	21922 + 50	to 21925 + 00	LT
	250	Sta.	21922 + 50	to 21925 + 00	RT
	185	Sta.	21925 + 00	to 21926 + 85	RT
	165	Sta.	21926 + 85	to 21928 + 50	RT
	175	Sta.	21928 + 50	to 21930 + 25	LT
	175	Sta.	21938 + 50	to 21940 + 25	RT
	175	Sta.	21940 + 25	to 21942 + 00	RT
	235	Sta.	21942 + 00	to 21944 + 35	LT
	235	Sta.	21942 + 00	to 21944 + 35	RT
	250	Sta.	21944 + 35	to 21946 + 85	LT
	250	Sta.	21944 + 35	to 21946 + 85	RT
	250	Sta.	21946 + 85	to 21949 + 35	LT
	250	Sta.	21946 + 85	to 21949 + 35	RT
TOTAL	4545				

PLOT DATE = Mon Mar 28 14:18:32 2005
 FILE NAME = c:\pms\mst\p21628\c1628sch.dgn
 PLOT SCALE = 1/8" = 1' IN
 USER NAME = jlljke