

# BITUMINOUS SCHEDULE

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Location	Remarks	Length	Proposed Surface		40600200	40600300	40600980	40800040	44000007	48202000	48202200	48202300	
			Width	Sq Yd	Bit Materials Prime Coat Ton	Agg Prime Coat Ton	Bit Surface Removal (Butt-Joint) Sq Yd	Incidental Bit Surfacing Ton	Bit Surface Removal 2" Sq Yd	Bit Shldrs, Superpave Ton	Bit Shldrs, Superpave, 4" Sq Yd	Bit Shldrs, Superpave, 5" Sq Yd	
<b>Ramp D-A / D-B Shoulders</b>													
Sta 65 + 58 - 66 + 48	LT	90	4 & Var	42.6	0.04	0.06				6.4			
Sta 65 + 58 - 66 + 48	RT	90	6 & Var	57.5	0.05	0.09				8.9			
Sta 66 + 48 - 66 + 53	LT	5	4 & Var	1.9	0.00	0.00						1.9	
Sta 66 + 48 - 67 + 37	RT	89	6 & Var	130.6	0.11	0.20		139.1		15.6			
<b>Ramp A-C / B-C Shoulders</b>													
Sta 80 + 23 - 81 + 62	RT	139	6 & Var	152.4	0.13	0.23		132.8		14.9			
Sta 80 + 98 - 81 + 62	LT	64	4 & Var	30.1	0.03	0.05							
Sta 81 + 62 - 82 + 52	RT	90	6 & Var	60.5	0.05	0.09	17.3			5.2			
Sta 81 + 62 - 82 + 52	LT	90	4 & Var	40.2	0.03	0.06		11.0		3.4			
<b>Limestone Road</b>													
Sta 90 + 12 - 90 + 75	Taper	63	Return	464.6	0.40	0.70	90.5	107.3					
Sta 90 + 23 - 90 + 75	Shldr LT	52	4 & Var	44.9	0.04	0.07	10.8						
Sta 90 + 23 - 90 + 75	Shldr RT	52	4 & Var	54.0	0.05	0.08	15.6						
<b>IL 72 (At Median Noses)</b>													
Sta 21926 + 44 - 21926 + 53	Widening	9	6 & Var	7.9	0.01	0.01							
Sta 21927 + 5 - 21927 + 89	Widening	84	6 & Var	40.6	0.03	0.06							
Sta 21939 + 63 - 21940 + 27	Widening	64	6 & Var	9.3	0.01	0.01							
Sta 21940 + 77 - 21941 + 83	Widening	106	6 & Var	44.4	0.04	0.07							
<b>S.B. I-39 Ramp C-A / C-B</b>													
Sta 23 + 30 - 24 + 14	Widening RT	84	8 & Var	70.2	0.06	0.11							
<b>S.B. I-39 Ramp A-D / B-D</b>													
Sta 30 + 31 - 31 + 36	Widening LT	105	4 & Var	42.0	0.04	0.06							
Sta 30 + 23 - 31 + 35	Widening RT	112	4 & Var	38.8	0.03	0.06							
<b>N.B. I-39 Ramp D-A / D-B</b>													
Sta 66 + 48 - 67 + 38	Widening RT	90	7 & Var	73.7	0.06	0.11							
<b>N.B. I-39 Ramp A-C / B-C</b>													
Sta 80 + 32 - 81 + 37	Widening LT	105	4 & Var	42.0	0.04	0.06							
Sta 80 + 23 - 81 + 34	Widening RT	111	5 & Var	52.0	0.04	0.08							
<b>ISLANDS</b>													
Sta 21926 + 50					0.01	0.02							
Sta 21940 + 0					0.01	0.02							
<b>TOTALS</b>					25,457	21.9	38.2	495	107	6,976	870	4,733	2,224

PLOT DATE: Mon Mar 28 14:18:38 2005  
 FILE NAME: c:\p\p\m\m\m\p\215280\alib280shdgn  
 PLOT SCALE: 50.0000 / IN.  
 USER NAME: jlljg