

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	BUREAU	60	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* SECTION 06-5, 06-6, 06-7, 06 & 50-81M				

EARTHWORK SCHEDULE

LOCATION	20200100 EARTH EXCAVATION (CUT)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
NEW CROSSOVERS					
FROM	TO				
3032+50.00	3041+00.00	993	505	745	966
3120+50.00	3129+00.00	938	505	704	1242
3256+50.00	3265+00.00	679		509	847
3645+50.00	3654+00.00	846		635	731
3732+50.00	3741+00.00	770		578	1085
3829+00.00	3836+50.00	511		383	789
	SUBTOTAL	4737		3553	5660
CROSSOVER REMOVALS					
FROM	TO				
3017+00.00	3017+75.00	159		119	0
3175+00.00	3175+75.00	131		98	0
3663+50.00	3664+50.00	86		65	0
3736+25.00	3737+00.00				
3854+00.00	3855+00.00	126		95	0
	SUBTOTAL	502		377	0
	TOTALS	5240		3930	5660
					-1730
		20200100 EARTH EXCAVATION			20400800 FURNISHED EXCAVATION
		5240 CU YD			1730 CU YD

25001830 SEEDING CLASS 6 (MODIFIED)		
NEW CROSSOVERS		
FROM	TO	ACRES
3032+50.00	3041+00.00	0.49
3120+50.00	3129+00.00	0.49
3256+50.00	3265+00.00	0.49
3645+50.00	3654+00.00	0.49
3732+50.00	3741+00.00	0.49
3829+00.00	3836+50.00	0.26
	SUBTOTAL	2.71
EXISTING CROSSOVER REMOVAL		
3017+00.00	3017+75.00	0.08
3175+00.00	3175+75.00	0.08
3663+50.00	3664+50.00	0.11
3736+25.00	3737+00.00	0.00
3854+00.00	3855+00.00	0.08
	SUBTOTAL	0.35
	TOTAL	3.00

25100115 MULCH METHOD 2		
NEW CROSSOVERS		
FROM	TO	ACRES
3032+50.00	3041+00.00	0.49
3120+50.00	3129+00.00	0.49
3256+50.00	3265+00.00	0.49
3645+50.00	3654+00.00	0.49
3732+50.00	3741+00.00	0.49
3829+00.00	3836+50.00	0.26
	SUBTOTAL	2.71
EXISTING CROSSOVER REMOVAL		
3017+00.00	3017+75.00	0.08
3175+00.00	3175+75.00	0.08
3663+50.00	3664+50.00	0.11
3736+25.00	3737+00.00	0.00
3854+00.00	3855+00.00	0.08
	SUBTOTAL	0.35
	TOTAL	3.00

25000400 NITROGEN FERTILIZER NUTRIENT		
NEW CROSSOVERS		
FROM	TO	POUNDS
3032+50.00	3041+00.00	44.1
3120+50.00	3129+00.00	44.1
3256+50.00	3265+00.00	44.1
3645+50.00	3654+00.00	44.1
3732+50.00	3741+00.00	44.1
3829+00.00	3836+50.00	23.4
	SUBTOTAL	243.9
EXISTING CROSSOVER REMOVAL		
3017+00.00	3017+75.00	7.4
3175+00.00	3175+75.00	7.4
3663+50.00	3664+50.00	9.9
3736+25.00	3737+00.00	0.0
3854+00.00	3855+00.00	7.0
	SUBTOTAL	31.8
	TOTAL	276

25000500 PHOSPHORUS FERTILIZER NUTRIENT		
NEW CROSSOVERS		
FROM	TO	POUNDS
3032+50.00	3041+00.00	44.1
3120+50.00	3129+00.00	44.1
3256+50.00	3265+00.00	44.1
3645+50.00	3654+00.00	44.1
3732+50.00	3741+00.00	44.1
3829+00.00	3836+50.00	23.4
	SUBTOTAL	243.9
EXISTING CROSSOVER REMOVAL		
3017+00.00	3017+75.00	7.4
3175+00.00	3175+75.00	7.4
3663+50.00	3664+50.00	9.9
3736+25.00	3737+00.00	0.0
3854+00.00	3855+00.00	7.0
	SUBTOTAL	31.8
	TOTAL	276

25000600 POTASSIUM FERTILIZER NUTRIENT		
NEW CROSSOVERS		
FROM	TO	POUNDS
3032+50.00	3041+00.00	44.1
3120+50.00	3129+00.00	44.1
3256+50.00	3265+00.00	44.1
3645+50.00	3654+00.00	44.1
3732+50.00	3741+00.00	44.1
3829+00.00	3836+50.00	23.4
	SUBTOTAL	243.9
EXISTING CROSSOVER REMOVAL		
3017+00.00	3017+75.00	7.4
3175+00.00	3175+75.00	7.4
3663+50.00	3664+50.00	9.9
3736+25.00	3737+00.00	0.0
3854+00.00	3855+00.00	7.0
	SUBTOTAL	31.8
	TOTAL	276

X0322392 BEVELED PIPE AND GUARD		
LOCATION	OFFSET	EACH
3034+60.00	CL	1
3038+95.00	CL	1
3122+60.00	CL	1
3126+95.00	CL	1
3258+60.00	CL	1
3262+95.00	CL	1
3647+60.00	CL	1
3651+95.00	CL	1
3734+60.00	CL	1
3738+95.00	CL	1
3830+41.00	CL	1
3835+13.00	CL	1
	TOTAL	12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY BRW
CHECKED BY RJA