

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	BUREAU	60	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* SECTION 06-5, 06-6, 06-7, 06 & 50-8M				

28000200 EARTH EXCAVATION FOR EROSION CONTROL		
AT TEMPORARY DITCH CHECKS		
LOCATION	CU YD	
3018+00.00	2.0	
3033+00.00	2.0	
3039+00.00	2.0	
3040+55.00	2.0	
3121+00.00	2.0	
3122+50.00	2.0	
3128+55.00	2.0	
3175+75.00	2.0	
3257+00.00	2.0	
3258+50.00	2.0	
3264+55.00	2.0	
3646+00.00	2.0	
3652+00.00	2.0	
3653+55.00	2.0	
3733+00.00	2.0	
3734+50.00	2.0	
3740+55.00	2.0	
3829+41.75	2.0	
3830+41.00	2.0	
3836+13.00	2.0	
3854+25.00	2.0	
TOTAL	42	

28000300 TEMPORARY DITCH CHECKS		
LOCATION	EACH	
3018+00.00	1	
3033+00.00	1	
3039+00.00	1	
3040+55.00	1	
3121+00.00	1	
3122+50.00	1	
3128+55.00	1	
3175+75.00	1	
3257+00.00	1	
3258+50.00	1	
3264+55.00	1	
3646+00.00	1	
3652+00.00	1	
3653+55.00	1	
3733+00.00	1	
3734+50.00	1	
3740+55.00	1	
3829+41.75	1	
3830+41.00	1	
3836+13.00	1	
3854+25.00	1	
TOTAL	21	

42000501 PCC PAVEMENT 10" (JOINTED)		
FROM	TO	SQ YD
3033+00.00	3040+55.00	2879.6
3121+00.00	3128+55.00	2879.6
3257+00.00	3264+55.00	2879.6
3646+00.00	3653+55.00	2879.6
3733+00.00	3740+55.00	2879.6
3829+41.75	3836+13.25	2077.6
TOTAL		16476

28000500 INLET AND PIPE PROTECTION		
AT NEW CROSSTOVERS		
LOCATION	EACH	
3038+95.00	1	
3122+60.00	1	
3258+60.00	1	
3651+95.00	1	
3734+60.00	1	
3830+41.75	1	
SUBTOTAL	6	
AT CROSSOVER REMOVAL		
3664+40.00	1	
SUBTOTAL	1	
TOTAL	7	

28000250 TEMPORARY EROSION CONTROL SEEDING		
NEW CROSSTOVERS		
FROM	TO	POUNDS
3032+50.00	3041+00.00	101.5
3120+50.00	3129+00.00	101.5
3256+50.00	3265+00.00	101.5
3645+50.00	3654+00.00	101.5
3732+50.00	3741+00.00	66.3
3829+00.00	3836+50.00	58.5
SUBTOTAL		530.8
EXISTING CROSSOVER REMOVAL		
3017+00.00	3017+75.00	8.3
3175+00.00	3175+75.00	8.3
3663+50.00	3664+50.00	11.0
3854+00.00	3855+00.00	7.8
SUBTOTAL		35.4
TOTAL		566

31100100 SUBBASE GRANULAR MATERIAL TYPE A			
FROM	TO	THICKNESS	TON
3033+00.00	3040+55.00	18"	3094.9
3121+00.00	3128+55.00	18"	3094.9
3257+00.00	3264+55.00	12"	2063.1
3646+00.00	3653+55.00	12"	2063.1
3733+00.00	3740+55.00	12"	2063.1
3829+41.75	3836+13.25	12"	1502.7
TOTAL			13882

42001300 PROTECTIVE COAT		
FROM	TO	SQ YD
3033+00.00	3040+55.00	2879.6
3121+00.00	3128+55.00	2879.6
3257+00.00	3264+55.00	2879.6
3646+00.00	3653+55.00	2879.6
3733+00.00	3740+55.00	2879.6
3829+41.75	3836+13.25	2077.6
TOTAL		16476

44004250 PAVED SHOULDER REMOVAL				
FROM	TO	OFFSET		SQ YD
3033+00.00	3040+55.00	28'RT TO 32'RT	EB	335.6
3033+00.00	3040+55.00	28'LT TO 32'LT	WB	335.6
3121+00.00	3128+55.00	28'RT TO 32'RT	EB	335.6
3121+00.00	3128+55.00	28'LT TO 32'LT	WB	335.6
3257+00.00	3264+55.00	28'RT TO 32'RT	EB	335.6
3257+00.00	3264+55.00	28'LT TO 32'LT	WB	335.6
3646+00.00	3653+55.00	28'RT TO 32'RT	EB	335.6
3646+00.00	3653+55.00	28'LT TO 32'LT	WB	335.6
3733+00.00	3740+55.00	28'RT TO 32'RT	EB	335.6
3733+00.00	3740+55.00	28'LT TO 32'LT	WB	335.6
3829+41.75	3836+13.25	21'RT TO 25'RT	EB	298.4
3829+41.75	3836+13.25	21'LT TO 25'LT	WB	298.4
TOTAL				3952

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY BRW
 HORIZ. CHECKED BY RJA
 DATE

DATE-TIME
 DGN-SPEC
 REF
 REF
 REF
 REF