

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	(126.127)RS-4	KENDALL	8	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

MAINLINE							
STATIONS	MIX FOR CRKS, JTS FLANGE	LEV BIND (HM) N50	BIT MAT PRIME COAT	AGG PR CT	BIT CONC SURF SUPER "C", N50	AGG SHLDS TYPE B	TEMP RAMP
	TON	TON	GALLON	TON	TON	TON	SQ YD
760+60 - 840+96	6.43	10.71	1714.3	42.9	1854.0	419.8	13.4
840+96 - 841+18	SN 047+0037						
841+18 - 964+25.88BK	10.06	16.77	2683.0	67.1	2901.6	642.9	6.7
963+16.53AH - 1037+78	5.97	9.95	1591.8	39.8	1721.5	389.8	6.7
1037+78 - 1038+62	SN 047+0014						
1038+62 - 1088+63	4.00	6.67	1066.9	26.7	1153.8	261.2	13.4
TOTALS	26	44	7056	176	7631	1714	40

PAVEMENT MARKING				
LOCATION	PAINT PAVT MK LINE 4"		PAINT PAVT MK LINE 6"	RAISED REFL PVT MARK
	WHITE FOOT	YELLOW FOOT	YELLOW FOOT	EACH
STA. TO STA.				
760+60 - 1088+63			7440	447
CENTERLINE				
EDGELINES	65824			
NO PASSING ZONES		14974		
TOTALS	65824	14974	7440	447

MILLING		
LOCATION	BITUMINOUS SURFACE REMOVAL	
	3/4"	BUTT JT
STA. TO STA.	SQ YD	SQ YD
760+60 - 761+20		160
761+20 - 840+36	21109	
840+36 - 840+96		160
SN 047-0037		
841+18 - 841+78		160
841+78 - 964+25.88BK	33377	
963+16.53AH - 1037+18	19737	
1037+18 - 1037+78		160
SN 047-0014		
1038+62 - 1039+22		160
1039+22 - 1088+03	13016	
1088+03 - 1088+63		160
TOTALS	87239	960

SIDEROADS AND ENTRANCES							
STATION	NUMBER	BIT MATLS PR CT	AGG PR CT	INC BIT SURF SUPER	BIT SURF REMOVAL 3/4"	TEMP RAMP	BIT SURF REMOVAL VAR DEPTH
		GALLON	TON	TON	SQ YD	SQ YD	SQ YD
COMMERCIAL ENTRANCES	2	10		15			120
PRIVATE ENTRANCES	17	44		40	336		140
MAILBOX TURNOUTS	10	22		35	280		
SIDEROADS	8	77	1.9	81		53	960
TOTALS		152	1.9	171	616	53	1220

DRAINAGE TABLE									
LOCATION	PIPE CULV TYPE 1 CL D 15"	END SECTIONS 15"	CONCRETE COLLAR	REINF BARS	EXP BOLTS 3/4'	GRADE AND SHAPE DITCH	CONCRETE HEADWALL REMOVAL	FURN EXC	EROSION CONTROL BLANKET (SEE NOTE)
	FOOT	EACH	CU YD	POUND	EACH	FOOT	CU YD	CU YD	SQ YD
APAKESHA ROAD									
SOUTHEAST QUAD	5	1	0.2	30	8	20	0.2	3	12
TOWNHOUSE ROAD									
SOUTHEAST QUAD	3	1				10	0.1	1.5	8
SOUTHWEST QUAD	3	1				10	0.1	1.5	8
TOTALS	11	3	0.2	30	8	40	0.4	6	28

NOTE: SEEDING, CLASS 2 SHALL BE PLACED IN THE AREAS OF THE EROSION CONTROL BLANKET. INCLUDED IN THE COST OF EROSION CONTROL BLANKET.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____

4/11/2005 9:42:00 AM c:\projects\66486\101\lshs.dgn