

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1279	1(D,E,F,P)1-3	LASALLE	19	3
STA. 23+51		TO STA. 35+09		
FED. ROAD DIST. NO.		ILLINOIS	NON-FED. AID PROJECT	

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:

X072-2A

CODE NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY
50102400	CONCRETE REMOVAL	CU YD	4.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4.3
50501130	STRUCTURAL STEEL REPAIR	POUND	7150
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	779
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1400
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1400
X0320887	POLYMER CONCRETE	CU FT	3.5
X0321743	SILICONE JOINT SEALER, 1"	FOOT	120
X0324943	FINGER PLATE ADJUSTMENT	FOOT	30
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0002600	BAR SPLICERS	EACH	32
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	70
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	635
Z0047300	PROTECTIVE SHIELD	SQ YD	1452
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1

* SFTY-3N

cmain05/cn326/det ails.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 EXISTING S.N. 050-0088
 IL 178 OVER ILLINOIS RIVER
 STATION 29+30

SCALE: VERT. _____
 HORIZ. _____
 DATE 12/08/04
 DRAWN BY RLW
 CHECKED BY _____