

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7R-3)	PEORIA	1360	24
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SET * - BILL OF MATERIALS FOR INFORMATION ONLY					URBAN IM										
					90 % FED 10 % STATE						90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE		
					ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F
(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert >20	Culvert <20, R Wall					War Memorial Dr/Sterling/Glen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance		
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY												
81400400	CONCRETE HANDHOLE	EACH	18								10		5	3	
81400600	CONCRETE DOUBLE HANDHOLE	EACH	2										1	1	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	7										4	3	
85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3									1	1	1	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2										1	1	
87900200	DRILL EXISTING HANDHOLE	EACH	3								3				
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	17										11	6	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6											6	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2										1	1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2										1	1	
89502380	REMOVE EXISTING HANDHOLE	EACH	13										8	5	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10										5	5	
M2010110	TREE REMOVAL 16 TO 15 UNITS DIAMETER	UNIT	4,931	3,731	1,200										
M2010500	TREE REMOVAL, HECTARES	HECTARE	2.0	0.3	1.7										
M2020010	EARTH EXCAVATION	CU M	121,628	3,048	118,580										
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	1,058							1,058					
M2040800	FURNISHED EXCAVATION	CU M	22,127	5,513	16,614										
M2070220	POROUS GRANULAR EMBANKMENT	CU M	16,074			562	552				14,960				
M2080250	TRENCH BACKFILL, SPECIAL	CU M	1,067	358	709										
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	76,307.0	56.0	76,251.0										
M2113100	TOP SOIL FURNISH AND PLACE, 100MM	SQ M	106,474	21,786	84,688										
M2500210	SEEDING, CLASS 2A	HA	9.7	1.2	8.5										
M2500350	SEEDING, CLASS 7	HA	8.5		8.5										
M2500400	NITROGEN FERTILIZER NUTRIENT	KILOGRAM	971	124	847										
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KILOGRAM	971	124	847										
M2500600	POTASSIUM FERTILIZER NUTRIENT	KILOGRAM	971	124	847										
M2510115	MULCH, METHOD 2	HECTARE	8.5		8.5										
M2510125	MULCH, METHOD 3	HECTARE	9.7	1.2	8.5										
M2510630	EROSION CONTROL BLANKET	SQ M	12		12										
M2520110	SODDING, SALT TOLERANT	SQ M	9,389	9,389											
M2520200	SUPPLEMENTAL WATERING	UNIT	3,000	3,000											
M2800900	FENCE (EROSION CONTROL)	METER	2,350	290	2,060										
M2810103	STONE RIPRAP, CLASS A2	SQ M	50		50										
M2810109	STONE RIPRAP, CLASS A5	SQ M	1,139								1,139				

FOR INFORMATION ONLY



REVISIONS	
NAME	DATE
	01/31/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 BILL OF MATERIALS
 WAR MEMORIAL DRIVE
 FAI ROUTE 74 (I-74) (WB)
 PLAN SET #1
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04