

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	49
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

GUARDRAIL EROSION CONTROL AGGREGATE SCHEDULE												
					STEEL PLATE BEAM GUARDRAIL, TYPE A	WIDTH	DEPTH	VOLUME	GUARDRAIL AGGREGATE EROSION CONTROL	GEOTEXTILE FABRIC	ARTICULATED BLOCK REVTMENT MAT	REMARK
LOCATIONS	STA	OFFSET	TO	STA	OFFSET	M	M	M	CU M	M TON	SQ M	SQ M
	144+150.000	15.08 M LT										208.87
	144+280.000	56.39 M LT										103.95
FAI ROUTE 74 (I-74)												
Ramp A-3	10+378.155	2.40 M RT	TO	10+385.000	2.30 M RT	10.75	0.75	0.20	2.0425	4.96	8.06	
	10+362.421		TO	10+341.421		10.02	0.75	0.20	1.9038	4.63	7.52	
Ramp B-2	10+726.331		TO	10+780.262	2.40 M RT	53.93	0.75	0.20	10.2467	24.90	40.45	
Ramp B-3	10+518.382	2.40M RT	TO	10+550.000	2.40M RT	31.62	0.75	0.20	6.0078	14.60	23.72	
	10+669.630(B3)	2.40M RT	TO	10+695.850(B3)		26.22	0.75	0.20	4.9818	12.11	19.67	
Ramp B-5	10+390.710(B5)	2.654 M RT	TO	10+419.620(B5)	2.654 M RT	28.91	0.75	0.20	5.4929	13.35	21.68	
MAINLINE WB	144+150.000	13.80 M RT	TO	144+250.000	13.80 M RT	100.00	0.75	0.20	19	46.17	75.00	
	144+250.000	13.80 M RT	TO	144+325.000	13.80 M RT	75.00	0.75	0.20	14.25	34.63	56.25	
	144+325.000	13.80 M RT	TO	144+718.000	13.80 M RT	393.00	0.75	0.20	74.67	181.45	294.75	
War Memorial Dr				39+910.000	45.00 M RT	75.00	0.75	0.20	14.25	34.63	56.25	
				TOTAL	1000-2A					34.63	56.25	
				TOTAL	J000-2A					337	547.1	312.8
				TOTAL						371	603	312.8
										J000-2A	J000-2A	J000-2A

EXPANSION JOINT SCHEDULE					
					EXPANSION JOINT 75 MM
LOCATIONS	STA	OFFSET	TO	STA	M
FAI ROUTE 74 (I-74)					
Ramp B 5				143+167.573	4.90
Ramp A 3				143+700.000	8.90
RAMP A 4				10+345.280	6.70
Ramp B 2				10+104.517	9.60
				TOTAL FOR J000-2A	30

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION GUARDRAIL EROSION CONTROL FAI ROUTE 74 (I-74) (WB) EXPANSION JOINT SCHEDULE
NAME	DATE	



DRAWN BY CADD
CHECKED BY RSC
DATE 11/12/04