

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-71R-3)	PEORIA	1360	51
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

				PERMANENT SEEDING SCHEDULE									
LOCATION	STA	TO	STA	LENGTH M	WIDTH M Avg	AREA 100MM TOP SOIL SQ M CADD	SODDING SALT TOLERANT SQ M	SUPPLEMENTAL WATERING UNIT	SEEDING CLASS 2A (L3 OR FLATTER) HA	NITROGEN FERTILIZER NUTRIENT KG	PHOSPHORUS FERTILIZER NUTRIENT KG	POTASSIUM FERTILIZER NUTRIENT KG	MULCH METHOD 3 OR FLATTER) HA (L3)
STAGE 3													
WAR MEM DRIVE	38+965.070	TO	39+150.000	184.93	3.97	734.87		2,000.00	0.07	7.35	7.35	7.35	0.07
	39+150.000	TO	39+500.000	350.00	6.96	2,437.50			0.24	24.38	24.38	24.38	0.24
Median	39+555.000		39+650.000	95.00	5.36	508.73	508.73						
	39+500.000	TO	39+850.000	350.00	10.29	3,600.00			0.36	36.00	36.00	36.00	0.36
Median	39+650.000		39+850.000	200.00	8.21	1,642.00	1,642.00						
	39+850.000	TO	40+175.000	325.00	8.32	3,662.50			0.37	36.63	36.63	36.63	0.37
Median	39+850.000		40+175.000	325.00	8.21	2,668.25	2,668.25						
	40+175.000	TO	40+480.82	90.00	21.80	1,962.00			0.20	19.62	19.62	19.62	0.20
Median	40+175.000		40+265.000	90.00	7.8	702.00	702.00						
Median	40+358.000		40+480.000	122.00	5.9	719.80	719.80						
	WAR MEM DR SUBTOTAL:					18,637.65	6,240.78	2,000.00	1.24	123.97	123.97	123.97	1.24
SCENIC DRIVE	10+050.000	TO	10+288.277	238.77									
MALL ACCESS	9+936.557	TO	9+986.557	50.00		3,148.20	3,148.20	1,000.00					
BRANDYWINE DR	39+385.798	TO	39+458.410	80.00									
GLEN AVENUE	101+038.000	TO	101+181.340	143.34									
STERLING AVE	100+910.908	TO	100+970.889	80.00									
	STAGE 3 SUBTOTAL:					106,474	9,389	3,000	9.7	971	971	971	9.7

WB I-74 SUBTOTAL:	18,248	-	-	2	182	182	182	2
RAMPS SUBTOTAL:	66,440	-	-	7	664	664	664	7
WAR MEM DR SUBTOTAL:	18,638	6,241	2,000	1	124	124	124	1
SCENIC DR SUBTOTAL:								
MALL ACCESS SUBTOTAL:								
BRANDYWINE DR SUBTOTAL:	3,148	3,148	1,000					
GLEN AVE SUBTOTAL:								
STERLING AVE SUBTOTAL:								
TOTAL	106,474	9,389	3,000	9.7	971	971	971	9.7
TOTAL FOR I000-2A	21,786	9,389	3,000	1.2	124	124	124	1.2
TOTAL FOR J000-2A	84,688	-	-	8.5	847	847	847	8.5



REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION PERMANENT SEEDING FAI ROUTE 74 (I-74) (WB)
NAME	DATE	
		DRAWN BY CADD CHECKED BY MWP DATE 11/12/04