


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	71
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	STA	TO	STA	LENGTH M	PIPE UNDERDRAINS				PIPE UNDERDRAINS 100mm (SPECIAL)		CONCRETE HEADW ALL FOR PIPE DRAINS EACH	
					150mm	150mm	100mm	100mm	LEFT	RIGHT		
					LEFT	RIGHT	LEFT	RIGHT	M	M		
I-74 MAINLINE, WB	141+900.000	TO	141+950.000	50.00	0.00	0.00	50.00	50.00	9.00	12.00	0	
I-74 MAINLINE, WB	141+950.000	TO	142+300.000	350.00	0.00	0.00	350.00	250.00	24.00	6.00	2	
I-74 MAINLINE, WB	142+300.000	TO	142+650.000	350.00	0.00	0.00	350.00	0.00	32.00	0.00	2	
I-74 MAINLINE, WB	142+650.000	TO	143+000.000	350.00	0.00	0.00	350.00	0.00	0.00	0.00	0	
I-74 MAINLINE, WB	143+000.000	TO	143+300.000	300.00	0.00	0.00	105.00	0.00	0.00	0.00	0	
I-74 MAINLINE, WB	143+300.000	TO	143+650.000	350.00	0.00	0.00	300.00	0.00	0.00	0.00	0	
I-74 MAINLINE, WB	143+650.000	TO	143+950.000	300.00	130.00	0.00	0.00	0.00	0.00	0.00	0	
I-74 MAINLINE, WB	143+950.000	TO	144+250.000	300.00	80.00	0.00	35.00	0.00	0.00	0.00	1	
I-74 MAINLINE, WB	144+250.000	TO	144+600.000	350.00	0.00	0.00	350.00	0.00	50.00	0.00	2	
I-74 MAINLINE, WB	144+600.000	TO	144+718.000	118.00	0.00	0.00	118.00	0.00	15.00	0.00	1	
RAMPS												
Ramp A-3	10+000.000	TO	10+172.000	201.02	0.00	172.00	0.00	0.00	0.00	0.00	0	
	10+172.000	TO	10+398.505	226.51	0.00	25.00	226.00	201.51	5.00	5.00	2	
	10+398.505	TO	10+432.516	BRIDGE								
	10+432.516	TO	10+528.000	95.48	0.00	0.00	95.48	95.48	30.00	30.00	4	
	10+528.000	TO	10+700.000	172.00	0.00	0.00	172.00	172.00	10.00	30.00	1	
Ramp A-4	10+200.000	TO	10+635.229	435.23	0.00	0.00	0.00	30.00	0.00	10.00	1	
Ramp B-1	10+137.966	TO	10+175.000	37.00	0.00	0.00	37.00	37.00	0.00	0.00	0	
	10+175.000	TO	10+700.000	525.00	265.00	0.00	260.00	525.00	25.00	40.00	4	
	10+700.000	TO	10+716.585	16.59	16.59	0.00	0.00	16.59	0.00	0.00	0	
	10+842.264	TO	10+950.000	107.74	107.74	0.00	0.00	60.00	0.00	20.00	2	
	10+950.000	TO	11+143.955	193.96	115.00	0.00	78.00	143.96	30.00	40.00	5	
Ramp B-2	10+000.000	TO	10+273.000	273.00	0.00	0.00	0.00	273.00	0.00	30.00	2	
	10+273.000	TO	10+580.000	305.00	0.00	0.00	82.00	385.00	2.00	30.00	2	
	10+580.000	TO	10+775.000	195.00	0.00	0.00	155.00	195.00	5.00	15.00	2	
	10+775.000	TO	10+825.000	50.00	0.00	0.00	0.00	50.00	15.00	30.00	3	
Ramp B-3	10+065.000	TO	10+196.000	131.00	0.00	0.00	0.00	76.00	0.00	0.00	0	
	10+196.000	TO	10+372.000	176.00	0.00	0.00	176.00	176.00	8.00	0.00	0	
	10+372.000	TO	10+586.000	214.00	0.00	0.00	30.00	214.00	16.00	8.00	2	
	10+586.000	TO	10+670.000	BRIDGE								
	10+670.000	TO	10+975.000	205.00	220.00	0.00	85.00	305.00	45.00	20.00	2	
	10+975.000	TO	11+195.000	220.00	0.00	0.00	195.00	220.00	30.00	30.00	4	
Ramp B-4	10+000.000	TO	10+192.000	192.00	0.00	0.00	75.00	85.00	35.00	35.00	6	
	10+192.000	TO	10+275.000	83.00	0.00	0.00	0.00	0.00	0.00	0.00	0	
	10+275.000	TO	10+445.000	15.00	0.00	0.00	0.00	15.00	0.00	0.00	0	
	10+445.000	TO	10+850.000	405.00	0.00	0.00	128.00	405.00	0.00	30.00	2	
	10+850.000	TO	10+972.450	122.45	0.00	0.00	122.45	122.45	30.00	15.00	3	
Ramp B-5	10+000.000	TO	10+550.000	550.00	206.00	0.00	170.00	452.00	0.00	0.00	0	
	10+550.000	TO	10+725.000	175.00	165.00	0.00	10.00	175.00	0.00	10.00	0	
	10+725.000	TO	10+927.000	202.00	0.00	0.00	177.00	202.00	0.00	0.00	0	
	10+927.000	TO	11+098.000	171.00	0.00	0.00	0.00	171.00	0.00	0.00	0	
Ramp B-6	10+000.000	TO	10+075.000	75.00	0.00	0.00	20.00	75.00	0.00	0.00	0	
	10+075.000	TO	10+270.000	195.00	0.00	0.00	105.00	195.00	0.00	30.00	0	
	10+270.000	TO	10+350.000	80.00	0.00	0.00	0.00	80.00	0.00	0.00	0	
TOTALS						1,305.3	197.0	4,406.9	5,453.0	416.0	476.0	55

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION UNDERDRAIN SCHEDULE FAI ROUTE 74 (I-74) (WB)
NAME	DATE	



DRAWN BY CADD
CHECKED BY RSC
DATE 11/12/04