


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION			PIPE DIAMETER d	LENGTH L	INSTALL TYPE	RIP RAP						FILTER FABRIC FOR RIP RAP	INLET AND PIPE PROTECTION EACH	
						CLASS A2		CLASS A6		CLASS B3				
STATION	TO	STATION	mm	M		THICKNESS	QUANTITY	THICKNESS	QUANTITY	THICKNESS	QUANTITY	SQ M		
						mm	SQ M	M TONS	mm	SQ M	M TONS	mm	SQ M	M TONS
BEDDING														
FAI ROUTE 74 WESTBOUND														
141+600.000	TO	141+950.000												5
			#1 900	5.0	A					300	7.3	3.9	7.3	
			#28 600	4.0	A					300	6.7	3.6	6.7	
141+950.000	TO	142+300.000												5
142+300.000	TO	142+650.000												5
142+650.000	TO	143+000.000												13
143+000.000	TO	143+300.000												15
			#8 375	4.0	A					300	1.9	1.0	1.9	
143+300.000	TO	143+650.000												43
			#23 525	4.0	A					300	2.4	1.3	2.4	
			#25 300	4.0	A					300	1.9	1.0	1.9	
			#27 300	4.0	A					300	1.9	1.0	1.9	
			#29 300	4.0	A					300	1.9	1.0	1.9	
			#34 375	4.0	A					300	1.9	1.0	1.9	
			#37 300	4.0	A					300	1.9	1.0	1.9	
			#49 600	4.0	A					300	6.7	3.9	6.7	
			#52 600	4.0	A					300	6.7	3.9	6.7	
			#54 300	3.0	B					300	8.6	4.6	8.6	
10+700.000 (B-1)	TO	10+75.000 (B-1)												14
			#69 300	3.0	B					300	8.6	4.6	8.6	
			#71 300	3.0	B					300	8.6	4.6	8.6	
			#73 300	3.0	B					300	8.6	4.6	8.6	
			#75 300	4.0	A					300	1.9	1.0	1.9	
			#76 750	5.0	A					300	6.0	3.2	6.0	
			#77 750	5.0	A					300	6.0	3.2	6.0	
143+650.000	TO	143+950.000												20
			#61 525	4.5	A					300	3.6	1.9	3.6	
			#65 600	4.5	A					300	3.6	1.9	3.6	
			#67 300	4.0	A					300	1.9	1.0	1.9	
143+950.000	TO	144+250.000												14
			#79 300	4.0	A					300	1.9	1.0	1.9	
			#82 900	5.0	A					300	7.3	3.9	7.3	
			#84 300	4.0	A					300	1.9	1.0	1.9	
			#85 300	4.0	A					300	1.9	1.0	1.9	
144+250.000	TO	144+600.000												4
144+600.000	TO	144+718.000												3
WAR MEMORIAL DRIVE														
38+965.067	TO	39+500.000												12
39+500.000	TO	39+600.000												27
39+600.000	TO	39+850.000												20
			#132 1200	8.0	A					450	49.4	39.6	49.4	
			OVERFLOW	-	A					300	74.9	40.0	74.9	
			#135 1200	8.0	4.0					300	47.5	25.3	47.5	
			EX. BOX	-	A	250.0	49.4	26.4	660	59.3	69.7			
			#142A 375	4.0	A					300	6.7	3.6	6.7	
39+850.000	TO	40+75.000												11
			#151 600	4.5	A					300	4.3	2.3	4.3	
			#154 300	3.0	A					300	1.9	1.0	1.9	
			#155 375	4.0	A					300	1.9	1.0	1.9	
			#157 300	3.0	A					300	1.9	1.0	1.9	
40+75.000	TO	40+500.000												26
			#162 375	4.0	A					300	1.9	1.0	1.9	
			#164 300	4.0	A					300	1.9	1.0	1.9	
			#165 525	4.5	A					300	3.6	1.9	3.6	
			#169 300	4.0	A					300	1.9	1.0	1.9	
40+500.000	TO	40+500.000												0
TOTALS							49.4	26.4	59.3	69.7	309.4	187.8	309.4	237

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION RIPRAP AND INLET PROTECTION FAI ROUTE 74 (1-74) (WB)
NAME	DATE	



DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04