

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	85
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TEMPORARY PAVEMENT MARKING SCHEDULE											
FAI ROUTE 74					TEMPORARY PAVEMENT MARKING TAPE, TYPE III					WET TEMPORARY PAVEMENT MARKING TAPE TYPE III	
					100 MM WHITE SOLID	100 MM YELLOW SOLID	100 MM WHITE SKIP-DASH	100 MM YELLOW SKIP-DASH	200 MM WHITE SOLID	100 MM WHITE SOLID	100 MM YELLOW SOLID
LOCATIONS	STATION	TO	STATION	LENGTH	M	M	M	M	M	M	

STAGE 3-1 (CONTINUE)

I-74 MAINLINE,	143+300.000	TO	143+650.000							
	143+300		143+650	350.0	700.0	700.0	175.0			
I-74 MAINLINE,	143+650.000	TO	143+950.000							
	143+650		143+805	155.0	155.0					
	143+650		143+950	300.0	300.0	600.0	150.0			
	143+805		143+950	145.0	145.0					
I-74 MAINLINE,	143+950.000	TO	144+250.000							
	143+950		144+250	300.0	300.0	600.0	150.0			
	144+178		144+250	72.0	72.0					
	143+950		144+178	228.0	228.0					
I-74 MAINLINE,	144+250.000	TO	144+325.000							
	144+250		144+325	75.0	150.0	150.0	37.5			
I-74 MAINLINE,	144+325.000	TO	144+600.000							
	144+325		144+600	275.0	550.0	550.0	137.5			
I-74 MAINLINE,	144+600.000	TO	144+718.000							
	144+600		144+718	118.0	236.0	236.0	59.0			
WAR MEMORIAL	38+965.070	TO	39+150.000							
	38+965		39+010	45.0		90.0				
	38+965		39+025	60.0	120.0		15.0			
	38+965		39+030	65.0	195.0		16.3			
	39+047		39+150	103.0	103.0					
	39+048		39+096	48.0	48.0					
	39+049		39+150	101.0			25.3			
	39+050		39+150	100.0	100.0					
	39+054		39+150	96.0	96.0		24.0			
	39+060		39+150	90.0		180.0				
STERLING AVE	100+911		101+000	89.0	267.0	178.0	44.5			
GLEN AVE	101+037		101+107	70.0	210.0		17.5			
GLEN AVE	101+050		101+107	57.0		114.0	14.3			
WAR MEMORIAL	39+150.000	TO	39+500.000							
	39+150		39+225	75.0	150.0					
	39+150		39+405	255.0	255.0	510.0	127.5			
	39+225		39+405	180.0			45.0			
	39+269		39+405	136.0	136.0					
	39+437		39+500	63.0	252.0	126.0	31.5			
WAR MEMORIAL	39+500.000	TO	39+850.000							
	39+500		39+555	55.0	55.0					
	39+500		39+610	110.0	110.0					
	39+500		39+850	350.0	700.0	700.0	175.0			
WAR MEMORIAL	39+850.000	TO	40+175.000							
	39+850		40+175	325.0	650.0	650.0	162.5			
WAR MEMORIAL	40+175.000	TO	40+481.000							
	40+175		40+481	306.0	612.0	612.0	153.0			

STAGE 3-1 SUBTOTAL I-74 (THIS SHEET)	2,836.0	2,836.0	709.0	0.0	0.0	0.0	0.0
SUBTOTAL I-74(STAGE)	7,913.0	6,723.0	1,081.6	0.0	0.0	635.0	200.0
SUBTOTAL WAR MEMORIAL DR	3,447.0	2,548.0	698.3	0.0	0.0	0.0	0.0
TOTAL STAGE 3-1	11,360.0	9,271.0	1,779.9	0.0	0.0	635.0	200.0
ROUNDED TOTAL STAGE 3-1	11,360	9,271	1,780	0	0	635	200

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 TEMPORARY PAVEMENT MARKING  
 FAI ROUTE 74 (I-74) (WB)  
 SCHEDULES

DATE 11/12/04

DRAWN BY CADD  
 CHECKED BY RSC

