


PERMANENT PAVEMENT MARKINGS SCHEDULE

FAI ROUTE 74				POLYUREA PAVEMENT MARKINGS TYPE I									EPOXY PAVEMENT
				LINE 100mm		LINE 150mm	LINE 200mm			LINE 300mm	LINE 600mm	LETTERS & SYMBOLS	
				SOLID	SOLID	DASH	SOLID	DASH	DOT	SOLID	SOLID		
				WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE		
LOCATIONS	STA	TO	STA	L	M	M	M	M	M	M	M	WHITE SM	
I-74 & RAMPS													
	141+900.00	TO	141+950.00										
I74 EB	141+900.000		141+950.000	50	50.00	50.00	12.50						
I74 WB	141+900.000		141+950.000	50	50.00	50.00	12.50						
	141+950.00	TO	142+300.000										
I74 EB	141+950.000		142+300.000	350	350.00	350.00	87.50						
I74 WB	141+950.000		142+205.000	255	255.00	255.00	63.75						
I74 WB	142+205.000		142+300.000	95		95.00	23.75			23.75			
RAMP A-4	10+540.000		10+635.000	95	95.00								
	142+300.00	TO	142+650.000										
I-74 EB	142+300.000		142+328.000	28	28.00	28.00	7.00						
I-74 EB	142+326.000		142+400.000	74		74.00	18.50			18.50			
I-74 EB	142+400.000		142+526.000	126		126.00	31.50	126.00					
I-74 EB	142+526.000		142+650.000	124	124.00	124.00	31.00						
I74 WB	142+300.000		142+460.000	160		160.00	40.00			40.00			
I74 WB	142+460.000		142+610.000	150		150.00	37.50	150.00					
I74 WB	142+610.000		142+650.000	40	40.00	40.00	10.00						
RAMP A-1	10+000.000		10+072.000	72	72.00								
RAMP A-1	10+072.000		10+199.000	127	127.00			127.00					
RAMP A-1	10+199.000		10+326.000	127	127.00	127.00							
A-1 GORE CHEVRONS										43.40			
RAMP A-4	10+190.000		10+225.000	35	35.00	35.00							
RAMP A-4	10+225.000		10+375.000	150	150.00			150.00					
RAMP A-4	10+375.000		10+540.000	165	165.00								
	142+650.00	TO	143+000.000										
I-74 EB	142+650.000		143+000.000	350	350.00	350.00	87.50						
I74 WB	142+650.000		142+880.000	230	230.00	230.00	57.50						
I74 WB	142+880.000		143+000.000	120		120.00	30.00			30.00			
RAMP A-1	10+326.000		10+375.000	49									
RAMP A-1	10+375.000		10+420.000	45						11.25			
RAMP A-1	10+420.000		10+500.000	80							4.38		
RAMP A-3	10+840.000		10+875.000	35	35.00	35.00				8.75			
RAMP A-3	10+875.000		10+980.000	105	105.00	105.00		105.00			10.80	2.46	
RAMP A-4	10+030.000		10+175.000	145	148.00	145.00	36.25						
RAMP B-5	11+234.000		11+354.000	120	120.00								
	143+000.00	TO	143+300.000										
I-74 EB	143+000.000		143+145.000	145	145.00	145.00	36.25						
I-74 EB	143+145.000		143+300.000	155		155.00	38.75	155.00					
I-74WB	143+000.000		143+140.000	140		140.00	35.00			35.00			
I-74WB	143+140.000		143+300.000	160		160.00	40.00	160.00					
RAMP A-2	10+240.000		10+440.000	200	200.00			200.00					
RAMP A-3	10+531.000		10+832.000	301	301.00	301.00							
RAMP A-3	10+832.000		10+840.000	8	8.00	8.00				2.00			
RAMP B-5	10+930.000		11+095.000	165	165.00								
RAMP B-5	11+095.000		11+234.000	139	139.00			139.00					
SUBTOTAL, I-74 & RAMPS (SHEET)					3,614.00	3,558.00	736.75	1,312.00	0.00	169.25	43.40	10.80	6.84

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-74R-3)	PEORIA	1360	93
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 PERMANENT PAVEMENT MARKING  
 FAI ROUTE 74 (I-74) (WB)  
 SCHEDULES  
 DRAWN BY CADD  
 CHECKED BY RSC  
 DATE 11/12/04