


| | | | | |
|---------------------|-----------|----------|------------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 74 | (72-7)R-3 | PEORIA | 1360 | 95 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

| PERMANENT PAVEMENT MARKINGS SCHEDULE | | | | | | | | | | | | | |
|---------------------------------------|-------------|----|-------------|-----------------------------------|----------|------------|------------|----------|-------|------------|------------|-------------------|------|
| FAI ROUTE 74 | | | | POLYUREA PAVEMENT MARKINGS TYPE I | | | | | | | | EPOXY PAVEMENT | |
| | | | | LINE 100mm | | LINE 150mm | LINE 200mm | | | LINE 300mm | LINE 600mm | LETTERS & SYMBOLS | |
| | | | | SOLID | SOLID | DASH | SOLID | DASH | DOT | SOLID | SOLID | | |
| | | | | WHITE | YELLOW | WHITE | WHITE | WHITE | WHITE | WHITE | WHITE | | |
| LOCATIONS | STA | TO | STA | L | M | M | M | M | M | M | M | SM | |
| I-74 & RAMPS CONTINUED | | | | | | | | | | | | | |
| | 143+950.00 | TO | 144+250.00 | | | | | | | | | | |
| I74EB | 143+950.000 | | 144+178.000 | 228 | 228.00 | 228.00 | 57.00 | | | | | | |
| I74EB | 144+178.000 | | 144+250.000 | 72 | | 72.00 | 18.00 | 72.00 | | | | | |
| I74WB | 143+950.000 | | 144+030.000 | 80 | 80.00 | 80.00 | 20.00 | | | | | | |
| I74WB | 144+030.000 | | 144+147.000 | 117 | | 117.00 | 29.25 | 117.00 | | | | | |
| I74WB | 144+147.000 | | 144+220.000 | 73 | | 73.00 | 18.25 | | | | | | |
| I74WB | 144+220.000 | | 144+250.000 | 30 | 30.00 | 30.00 | 15.00 | | | | | | |
| RAMP B-2 | 10+000.000 | | 10+075.000 | 75 | 75.00 | | 18.75 | | | | | | |
| RAMP B-2 | 10+075.000 | | 10+193.000 | 118 | 118.00 | | 29.50 | 118.00 | | | | | |
| RAMP B-2 | 10+193.000 | | 10+274.000 | 81 | 81.00 | 81.00 | 20.25 | | | | | | |
| B-2 GORE CHEVRONS | | | | | | | | | | 56.40 | | | |
| RAMP B-4 | 10+850.000 | | 11+044.000 | 194 | 194.00 | 194.00 | | | | | | | |
| RAMP B-4 | 11+044.000 | | 11+115.000 | 71 | 71.00 | | | 71.00 | | | | | |
| | 144+250.00 | TO | 144+600.00 | | | | | | | | | | |
| I74EB | 144+250.000 | | 144+440.000 | 190 | | 190.00 | 47.50 | 190.00 | | | | | |
| I74EB | 144+440.000 | | 144+600.000 | 160 | 160.00 | 160.00 | 80.00 | | | | | | |
| I74WB | 144+250.000 | | 144+600.000 | 350 | 350.00 | 350.00 | 175.00 | | | | | | |
| RAMP B-4 | 11+115.000 | | 11+261.000 | 146 | 146.00 | | | 146.00 | | | | | |
| | 144+600.00 | TO | 144+718.00 | | | | | | | | | | |
| I74EB | 144+600.000 | | 144+718.000 | 118 | 118.00 | 118.00 | 59.00 | | | | | | |
| I74WB | 144+600.000 | | 144+718.000 | 118 | 118.00 | 118.00 | 59.00 | | | | | | |
| | 39+500.000 | TO | 39+850.000 | | | | | | | | | | |
| RAMP B-3 | 10+975.000 | | 11+142.000 | 167 | 167.00 | 167.00 | | | | | | | |
| RAMP B-3 | 11+142.000 | | 11+156.000 | 14 | 14.00 | | | 14.00 | | | | | |
| RAMP B-3 | 11+156.000 | | 11+185.000 | 29 | 29.00 | | | | | | | | |
| | 39+850.000 | TO | 40+175.000 | | | | | | | | | | |
| RAMP B-3 | 10+556.000 | | 10+975.000 | 419 | 419.00 | 419.00 | | | | | | | |
| RAMP B-5 | 10+023.000 | | 10+035.000 | 12 | | | | | | | | | |
| RAMP B-5 | 10+035.000 | | 10+042.000 | 7 | 7.00 | | | | | | | | |
| RAMP B-5 | 10+042.000 | | 10+060.000 | 18 | 18.00 | | | | | | | | |
| RAMP B-5 | 10+060.000 | | 10+070.000 | 10 | 10.00 | | | 10.00 | | | | | |
| RAMP B-5 | 10+070.000 | | 10+550.000 | 480 | 480.00 | 480.00 | | | | | | | |
| RAMP B-6 | 10+000.000 | | 10+023.000 | 23 | 23.00 | | | | | | | | |
| RAMP B-6 | 10+023.000 | | 10+045.000 | 22 | 22.00 | | | | | | | | |
| RAMP B-6 | 10+045.000 | | 10+055.000 | 10 | 10.00 | | | 10.00 | | | | | |
| RAMP B-6 | 10+055.000 | | 10+075.000 | 20 | 20.00 | 20.00 | | | | | | | |
| SUBTOTAL, I-74 & RAMPS (SHEET) | | | | | 2,988.00 | 2,897.00 | 646.50 | 748.00 | 0.00 | 0.00 | 56.40 | 0.00 | 0.00 |
| SUBTOTAL, I-74 & RAMPS (SHEETS 1 - 3) | | | | | 0,564.00 | 0,425.00 | 1,797.00 | 2,977.00 | 0.00 | 191.75 | 265.30 | 10.80 | 6.84 |



| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION PERMANENT PAVEMENT MARKING FAI ROUTE 74 (I-74) (WB) SCHEDULES |
|-----------|------|--|
| NAME | DATE | |
| | | DRAWN BY CADD CHECKED BY RSC DATE 11/12/04 |
| | | |
| | | |
| | | |
| | | |
| | | |