

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-74R-3)	PEORIA	1360	882
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SET #2 BILL OF MATERIALS FOR INFORMATION ONLY				URBAN / IM													
				90% FED 10% STATE										90% FED 5% STATE 5% CITY		90% FED 10% CITY	
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
28000300	TEMPORARY DITCH CHECKS	EACH	47		47												
28000500	INLET AND PIPE PROTECTION	EACH	28		28												
28000510	INLET FILTER	EACH	53		53												
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1												
51500100	NAME PLATES	EACH	3						1	2							
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	20		20												
60246605	MEDIAN INLET (604101)	EACH	1		1												
60246805	MEDIAN INLET (604106)	EACH	1		1												
60247132	DRAINAGE STRUCTURES, TYPE 1A WITH ONE TYPE 20 FRAME AND GRATE	EACH	3		3												
60258100	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1		1												
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1		1												
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4												
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4		4												
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	2		2												
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	384		384												
78200410	GUARDRAIL MARKERS, TYPE A	EACH	37		37												
78200500	BARRIER WALL MARKERS	EACH	8		8												
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4												
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	151		151												
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	310		310												
M2010500	TREE REMOVAL, HECTARES	HA	0.9		0.9												
M2020010	EARTH EXCAVATION	CU M	31,470		31,470												
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	120		120												
M2080250	TRENCH BACKFILL, SPECIAL	CU M	223		223												
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO M	33,159.5		33,159.5												
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SO M	30,420		30,420												
M2500210	SEEDING, CLASS 2A	HA	2.8		2.8												
M2500300	SEEDING, CLASS 3	HA	0.5		0.5												
M2500350	SEEDING, CLASS 7	HA	3.0		3.0												
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	304.3		304.3												
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	304.3		304.3												
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	304.3		304.3												
M2510125	MULCH, METHOD 3	HA	2.6		2.6												
M2510630	EROSION CONTROL BLANKET	SO M	4,196.9		4,196.9												

\* SPECIALTY ITEMS  
+ FUND CODE SFTY-3N  
++ FUND CODE Y080  
+++ FUND CODE SFTY-3C  
Δ NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
- (3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183
- (4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005)
- (5) WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
- (6) WAR MEMORIAL DRIVE / STERLING / GLEN
- (7) WAR MEMORIAL DRIVE / SCENIC DRIVE
- (8) SCENIC DRIVE / WALL ENTRANCE



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**TOTAL BILL OF MATERIALS**  
**PLAN SET #2**  
FAI ROUTE 74 (I-74)  
DRAWN BY RDY  
CHECKED BY LSA  
DATE 11/23/04

11/23/04 10:00 AM 11/23/04 10:00 AM 11/23/04 10:00 AM 11/23/04 10:00 AM 11/23/04 10:00 AM