

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-70R-3	PEORIA	1360	708
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		


EROSION CONTROL GENERAL NOTES

PRIOR TO BEGINNING EARTHWORK OR STRUCTURE REMOVAL, PERIMETER BARRIER SHALL BE PLACED AS GIVEN IN ACCORDANCE WITH THE TYPICAL APPLICATION OF THE SILT FENCE DETAIL AND SECTION 280 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND AS DIRECTED BY THE RESIDENT ENGINEER.

RIP RAP AND SEEDING, WITH EROSION CONTROL FIBER BLANKET SHALL BE PLACED IMMEDIATELY AFTER FINAL GRADING FOR PROPOSED DITCHES IN ACCORDANCE WITH SECTIONS 250, 251, 281 AND 282 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND AS DIRECTED BY THE RESIDENT ENGINEER.

DURING THE CONSTRUCTION OPERATIONS WHEN ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR DRAINAGE STRUCTURES SO THE NATURAL FLOW OF WATER IS OBSTRUCTED, THE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS ALL DRAINAGE STRUCTURES SHALL BE FREE FROM ALL DIRT AND DEBRIS CAUSED BY THE CONSTRUCTION. THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED AS INCLUDED IN THE COST OF THE ASSOCIATED PAY ITEMS.

REFER TO THE STORM WATER POLLUTION PREVENTION PLAN FOR ADDITIONAL INFORMATION AND REQUIREMENTS.



CLARK ENGINEERS, INC.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

EROSION CONTROL
GENERAL NOTES
FAI ROUTE 74 (I-74)

DATE 11/23/04
DRAWN BY CAM
CHECKED BY LSA