

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	18
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

\* (90-111R-2)90(13,14,14-1)R-1

SUMMARY OF QUANTITIES FOR ALL PLAN SETS				URBAN												
				IM						IM						
				90% FED 10% STATE						90% FED 10% STATE						
				CONSTRUCTION TYPE CODE												
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) I000-2A	ARTERIAL ROADWAY (3) I000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X271-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F
M6021485	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 37 GRATE	EACH	6.0		5.0		1.0									
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12				11	1								
M6021805	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2												
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	1	1											
M6021845	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1												
M6023005	MANHOLES, SPECIAL, 1.2M DIAMETER	EACH	1		1											
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	28	2.7	17.2		1	6.6								
M6060260	CONCRETE GUTTER, TYPE A	METER	181	139.6				41								
M6060270	CONCRETE GUTTER, TYPE A (MODIFIED)	METER	843	499.7	342.8											
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	871	84	50.2		368	368.84								
M6060600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45	METER	33.0	33.0												
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	4381.0		88.0		2888.0	1405.0								
M6062100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.15	METER	22.7		12.7		10.0									
M6062400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.60	METER	18.2		7.2		11.0									
M6063600	CONCRETE MEDIAN SURFACE, 100MM	SQ M	2133.3		23.0		17.0	2093.3								
M6064100	CONCRETE MEDIAN, TYPE SB-15.30	SQ M	374.0					374.0								
M6064800	CONCRETE MEDIAN, TYPE SM	SQ M	12.0				12.0									
M6066000	CORRUGATED MEDIAN	SQ M	57.1		6.0			51.1								
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	259	11.43	198.12		49.53									
M6320030	GUARDRAIL REMOVAL	METER	1283	703	284	57	42	197								
M6330610	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	METER	1291		1291											
M6370120	CONCRETE BARRIER, DOUBLE FACE (MODIFIED)	METER	566	566												
M6370140	CONCRETE BARRIER, SINGLE FACE (MODIFIED)	METER	1372.00	1372.00												
M6420015	SHOULDER RUMBLE STRIP	METER	19080	2940	2937.325	13202.2										
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	192.00	192.00												
M6640120	CHAIN LINK FENCE, 1.8 METER	METER	29		28.5											
M6640650	CHAIN LINK GATES, 1.8M X 2.4M SINGLE	EACH	1		1											
M6641920	CHAIN LINK FENCE REMOVAL	METER	165	165												
M6641930	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	METER	187.0		187.0											
M7030100	SHORT- TERM PAVEMENT MARKING	METER	24194.9	20993.0		2849.0		352.9								
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	12568		1367	11201										
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	1400			1400										
M7030250	TEMPORARY PAVEMENT MARKING - LINE 200MM	METER	527			527										
* M7030510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ M	98	98												
* M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	29947	25993	3954											
* M7030540	PAVEMENT MARKING TAPE, TYPE III 150MM	METER	749	749												

- △ SFTY-3N
- SFTY-3C
- Y080
- NON-PARTICIPATING
- \* SPECIALTY ITEM

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+392.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY

CHECKED BY

02/14/2005 11:22:52 AM q:\data\55893-74\dwg\contract\packaging\sq\08p-6a.dgn

CONTRACT IN PACKAGING PAGE 18 OF 25 FINAL PLANS 01/17/05