

I:\Projects\11102-6002-DR-1\11/10/2005 8:44:56 AM

68201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	00-10R-20011414-DR-1	TAZEWELL	1366	28
STA.			TO STA.	
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

PROJECT SPECIFIC NOTES

CROSS SECTIONS

IN THE CROSS SECTIONS USE THE FOLLOWING LEGENDS WITH END AREAS COMPUTED IN m²

SPECIAL EXCAVATION	S
UNSUITABLE MATERIAL	U
EARTH EXCAVATION	E
EMBANKMENT	F
TOPSOIL FURNISH AND PLACE	T

FINAL FINISH ON PORTLAND CEMENT CONCRETE PAVEMENT

A TYPE "A" FINAL FINISH SHALL BE PROVIDED ON I-74 MAINLINE, RAMP AND MAIN STREET PCC PAVEMENTS.

A TYPE "B" FINAL FINISH, OBTAINED IN ACCORDANCE WITH ARTICLE 420.11(E)(2) OF THE STANDARD SPECIFICATIONS, SHALL BE PROVIDED ON OFF SYSTEM STREET PCC PAVEMENTS EXCEPT MAIN STREET.

ACCESS CONTROL FENCE

THE CONTRACTOR SHALL TEMPORARILY RE-ERECT ACCESS CONTROL FENCE UNLESS CONSTRUCTION OPERATIONS ARE ON GOING AND WORKERS ARE PRESENT UNTIL THE PERMANENT ACCESS CONTROL FENCE IS INSTALLED. THIS WORK INCLUDING ADDITIONAL TEMPORARY FENCE REQUIRED TO MAINTAIN THE INTEGRITY OF THE ACCESS CONTROL FENCE SHALL BE INCLUDED IN THE COST OF PERMANENT FENCE.

EXISTING DRAINAGE:

THE CONTRACTOR SHALL VERIFY ALL EXISTING ELEVATIONS CRITICAL TO THE PROPOSED DRAINAGE PATTERNS IN SET 1 OF 4 PRIOR TO PERFORMING ANY DRAINAGE RELATED WORK. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF ANY DISCREPANCIES ARE FOUND.

TEMPORARY CONCRETE BARRIER:

ANY TEMPORARY CONCRETE BARRIER TO BE REMOVED AND RELOCATED THAT IS NOT NEEDED FOR THE NEXT SUBSEQUENT STAGE OF CONSTRUCTION SHALL BE STORED IN A MANNER AND LOCATION THAT DOES NOT INTERFERE WITH CONSTRUCTION. THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED AS INCLUDED IN THE PAY ITEMS PROVIDED.

EARTHWORK STAGING:

EARTHWORK QUANTITIES DESIGNATED AS STAGE 3A-1 IN THE CROSS SECTIONS ARE SCHEDULED AS STAGE 3A.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

DATE 12/20/04

DRAWN BY SRS
CHECKED BY JUM

