

No. 95-11-E-5002/L1 ufp 5005-10118V (Ampro)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	31
TO STA.				
ILLINOIS FED. AID PROJECT				

\*(90-11R-2;90(13,14,14-1R-1

**BILL OF MATERIALS FOR SET 1 OF 4  
FOR INFORMATION ONLY**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN															
				IM 90% FED 10% STATE			BRI 80% FED 20% STATE			IM 90% FED 10% STATE									
				CONSTRUCTION TYPE CODE															
				INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) I000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F							
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	20																20
88800100	PEDESTRIAN PUSH-BUTTON	EACH	2																2
89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L SUM	2																2
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1																1
89502380	REMOVE EXISTING HANDHOLE	EACH	5																5
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5																5
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	267				214	53											
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	176	94	64	18													
M2010500	TREE REMOVAL, HECTARES	HA	1.0	0.7	0.3														
M2011000	TEMPORARY FENCE	METER	1703	1703															
M2020010	EARTH EXCAVATION	CU M	52183	51470		713													
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	1668	1105	563														
M2021400	SUB-BASE GRANULAR MATERIAL, TYPE A	M TON	11751			11751													
M2021500	SUB-BASE GRANULAR MATERIAL, TYPE B	M TON	6512		6512														
M2040800	FURNISHED EXCAVATION	CU M	3400		3713	-313													
M2070220	POROUS GRANULAR EMBANKMENT	CU M	2831				502	360	111									1858	
M2080250	TRENCH BACKFILL, SPECIAL	CU M	508	281	175	52													
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	25607.0	25607.0															
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQ M	46954	20608	17528	8818													
M2500110	SEEDING, CLASS 1A	HA	3.9	3.9															
M2500312	SEEDING, CLASS 4A	HA	3.1	3.1															
M2500322	SEEDING, CLASS 5A	HA	0.4	0.4															
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	377	377															

- (1) WB I-74 STA 152+445.837 TO STA 153+892.180
- (2) MAIN STREET STA 2+800.000 TO STA 4+157.000
- (3) MAIN STREET STA 2+402.933 TO STA 2+800.000
- (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)
- BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET)
- (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)
- (7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
- RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

REVISIONS	
NAME	DATE

**ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 74 (I-74)**

**TOTAL BILL OF MATERIALS**

DRAWN BY MLS  
CHECKED BY JJM

DATE 12-20-04

