

Rd 90.11 E 9002/11 ubf 5955-1011151 Newpoc

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		TAZEWELL	136	33
TO STA.				
ILLINOIS FED. AID PROJECT				

*190-11R-2:9013,14,14-11R-1

BILL OF MATERIALS FOR SET 1 OF 4
FOR INFORMATION ONLY

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN										
				IM 90% FED 10% STATE			BRI 80% FED 20% STATE			IM 90% FED 10% STATE				
				CONSTRUCTION TYPE CODE										
INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) I000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F						
M4205200	PROTECTIVE COAT	SQ M	48105	29768	2757	15580								
M4210290	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 290MM	SQ M	10820	10820										
M4214290	PAVEMENT REINFORCEMENT 290MM	SQ M	10820	10820										
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	286		99	187								
M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	91.0	55.0		36.0								
M4400025	BITUMINOUS SURFACE REMOVAL 25MM	SQ M	24929		24929									
M4400050	BITUMINOUS SURFACE REMOVAL 50MM	SQ M	21			21								
M4402000	PAVEMENT REMOVAL	SQ M	12288	12288										
M4402020	CURB REMOVAL	METER	300	300										
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	119	119										
M4402280	CONCRETE BARRIER REMOVAL	METER	67	67										
M4402530	PAVED SHOULDER REMOVAL	SQ M	7998	7998										
M4405000	PAVED DITCH REMOVAL	METER	480	480										
M4426225	CLASS B PATCHES, TYPE II, 250MM	SQ M	709		709									
M4426450	CLASS B PATCHES, TYPE IV, 375MM	SQ M	113	113										
M4429400	SAW CUTS	METER	856	71	785									
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	5528		5528									
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	660	660										
M4820200	BITUMINOUS SHOULDERS 200MM	SQ M	514	514										
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250MM	SQ M	4195	4040		155								
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290MM	SQ M	3545	3545										
M5010240	CONCRETE REMOVAL	CU M	122.2								122.2			
M5010465	SLOPE WALL REMOVAL	SQ M	306								306			

SHEET 5 OF 15

- | | |
|--|---|
| (1) WB I-74 STA 152+445.837 TO STA 153+892.180 | (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)
BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET) |
| (2) MAIN STREET STA 2+800.000 TO STA 4+157.000 | (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
(6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET) |
| (3) MAIN STREET STA 2+402.933 TO STA 2+800.000 | (7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
(8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
RETAINING WALL SN 090-8513 (ALONG RAMP K-2) |

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)
TOTAL BILL OF MATERIALS
 DATE 12-20-04
 DRAWN BY MLS
 CHECKED BY JJM