BILL OF MATERIALS FOR SET 1 OF 4

FOR INFORMATION ONLY

				URBAN								
				IM 90% FED 10% STATE			BRI 80% FED 20% STATE		IM 90% FED 10% STATE			
				CONSTRUCTION TYPE CODE								
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) I000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F
M5120160	FURNISHING STEEL PILES HP310X79	METER	132.0							132.0		
M5120166	FURNISHING STEEL PILES HP310X94	METER	292.0				292.0					
M5120170	FURNISHING STEEL PILES HP310X110	METER	504.0				504.0					
M5120175	FURNISHING STEEL PILES HP310X125	METER	603.5					603.5				
M5120180	FURNISHING STEEL PILES HP360X108	METER	524.5							524.5		
M5120190	FURNISHING STEEL PILES HP360X132	METER	186.0						186.0			
M5120210	FURNISHING STEEL PILES HP360X174	METER	627.0					627.0				
M5120315	DRIVING STEEL PILES	METER	2868.5				796.0	1230.0	186.0	656.5		
M5120460	TEST PILE STEEL HP310X79	EACH	2							2		
M5120475	TEST PILE STEEL HP310X125	EACH	1					1				
M5120480	TEST PILE STEEL HP360X108	EACH	1							1		
M5120490	TEST PILE STEEL HP360X132	EACH	2						2			
M5120510	TEST PILE STEEL HP310X174	EACH	1					1				
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	25		16	9						
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	3		2	1						
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	6	2	4							
M542E136	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 750MM	EACH	4		3	1						
M542E536	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 750MM	EACH	1			1						
M542F012	METAL END SECTIONS 300MM	EACH	12	12								
M542I055	PIPE CULVERTS, CLASS A, TYPE 2 900MM	METER	29.0	29.0								
M542U425	PIPE CULVERTS, CLASS D, TYPE 2 450MM (TEMPORARY)	METER	4.0	4.0								
M5429910	CONCRETE COLLAR	CU M	3.5		2.4	1.1						
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	396.0	9.0	186.0	201.0						
M5500050	STORM SEWERS, CLASS A, TYPE 1 450MM	METER	107.0		103.0	4.0						

(1) WB I-74 STA 152+445.837 TO STA 153+892.180

(2) MAIN STREET STA 2+800.000 TO STA 4+157.000

(3) MAIN STREET STA 2+402.933 TO STA 2+800.000

(4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)
BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET)

(5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)

(6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)

(7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)

(8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

REVISIONS	
NAME	DATE

URS
URS CORPORATION
DECATUR, ILLINOIS

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)

TOTAL BILL OF MATERIALS

DRAWN BY MLS
DATE 12-20-04
CHECKED BY JJM

...\roadway\ed01101-bd85j.dgn 1/7/2005 3:11:20 PM