

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1566	36
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*(90-11R-2;90(13,14,14-1R-1

**BILL OF MATERIALS FOR SET 1 OF 4
FOR INFORMATION ONLY**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN										
				IM 90% FED 10% STATE			BRI 80% FED 20% STATE			IM 90% FED 10% STATE				
				CONSTRUCTION TYPE CODE										
INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) 1000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F						
M5500065	STORM SEWERS, CLASS A, TYPE 1 600MM	METER	23.5		23.5									
M5500070	STORM SEWERS, CLASS A, TYPE 1 675MM	METER	6.0		6.0									
M5500075	STORM SEWERS, CLASS A, TYPE 1 750MM	METER	77.0	63.5	3.0	10.5								
M5500430	STORM SEWERS, CLASS A, TYPE 2 300MM	METER	364.0	104.0	260.0									
M5500450	STORM SEWERS, CLASS A, TYPE 2 450MM	METER	189.5		162.5	27.0								
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	647.5	511.5	136.0									
M5500475	STORM SEWERS, CLASS A, TYPE 2 750MM	METER	128.0		124.0	4.0								
M5500830	STORM SEWERS, CLASS A, TYPE 3 300MM	METER	64.5		64.5									
M5500865	STORM SEWERS, CLASS A, TYPE 3 600MM	METER	42.5	42.5										
M5501230	STORM SEWERS, CLASS A, TYPE 4 300MM	METER	17.5		17.5									
M5501275	STORM SEWERS, CLASS A, TYPE 4 750MM	METER	16.5		16.5									
M5510025	STORM SEWER REMOVAL 300MM	METER	9.5			9.5								
M5510040	STORM SEWER REMOVAL 400MM	METER	46.0	46.0										
M5510060	STORM SEWER REMOVAL 600MM	METER	45.5	37.0	8.5									
M5510070	STORM SEWER REMOVAL 750MM	METER	2.5		2.5									
M5510080	STORM SEWER REMOVAL 900MM	METER	6.5		6.5									
M5870020	BRIDGE SEAT SEALER	SQ M	115					42	73					
M5900100	EPOXY CRACK SEALING	METER	34						34					
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	781								781			
M6010080	FRENCH DRAINS	CU M	29								29			
M6010125	PIPE DRAINS 300MM	METER	218.5	218.5										
M6010605	PIPE UNDERDRAINS 100MM	METER	973.0	973.0										
M6010610	PIPE UNDERDRAINS 150MM	METER	24.5		24.5									

- (1) WB I-74 STA 152+445.837 TO STA 153+892.180
- (2) MAIN STREET STA 2+800.000 TO STA 4+157.000
- (3) MAIN STREET STA 2+402.933 TO STA 2+800.000

- (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)
BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET)
- (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)
- (7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

REVISIONS	
NAME	DATE

**ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)**

TOTAL BILL OF MATERIALS

DRAWN BY MLS
CHECKED BY JJM

DATE 12-20-04

