

Rd. 6E-11, E. 9002/1/1 ufo-58995-101185\tempo01

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\*90-11R-2;9013,14,14-11R-1

**BILL OF MATERIALS FOR SET 1 OF 4**  
**FOR INFORMATION ONLY**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN									
				IM 90% FED 10% STATE			BRI 80% FED 20% STATE			IM 90% FED 10% STATE			
				CONSTRUCTION TYPE CODE									
				INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) I000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F	
M6010705	PIPE UNDERDRAINS 100MM (SPECIAL)	METER	1435.0	1435.0									
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1		1								
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	18	1	14	3							
M6021445	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 9 FRAME AND GRATE	EACH	2	2									
M6021485	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 37 GRATE	EACH	1		1								
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12		11	1							
M6021805	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2									
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
M6021845	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1									
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	10.3	2.7	1.0	6.6							
M6060260	CONCRETE GUTTER, TYPE A	METER	180.6	139.6	41.0								
M6060270	CONCRETE GUTTER, TYPE A (MODIFIED)	METER	499.7	499.7									
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	452.0	84.0	368.0								
M6060600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45	METER	33.0	33.0									
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	3819.0		2888.0	931.0							
M6062100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.15	METER	10.0		10.0								
M6062400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.60	METER	11.0		11.0								
M6063600	CONCRETE MEDIAN SURFACE, 100MM	SQ M	1346		17	1329							
M6064100	CONCRETE MEDIAN, TYPE SB-15.30	SQ M	156			156							
M6064800	CONCRETE MEDIAN, TYPE SM	SQ M	12		12								
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	60.96	11.43	49.53								
M6320030	GUARDRAIL REMOVAL	METER	942	703	42	197							
M6370120	CONCRETE BARRIER, DOUBLE FACE (MODIFIED)	METER	566	566									

SHEET 9 OF 15

- (1) WB I-74 STA 152+445.837 TO STA 153+892.180
- (2) MAIN STREET STA 2+800.000 TO STA 4+157.000
- (3) MAIN STREET STA 2+402.933 TO STA 2+800.000

- (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)  
BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET)
- (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)
- (7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)  
RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 74 (I-74)

**TOTAL BILL OF MATERIALS**



DATE 12-20-04  
DRAWN BY MLS  
CHECKED BY JJM