

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*	TAZEWELL	1366	40
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (90-IBR-2:90013,14,14-DR-1

BILL OF MATERIALS FOR SET 1 OF 4
FOR INFORMATION ONLY

				URBAN									
				IM 90% FED 10% STATE		BRI 80% FED 20% STATE		IM 90% FED 10% STATE					
				CONSTRUCTION TYPE CODE									
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) I000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F	
M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	3.0									3.0	
MX030199	TEMPORARY PAVEMENT	SQ M	12378	6525		5853							
MX030345	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU M	51.7								51.7		
MX030396	FILL EXISTING STORM SEWERS	CU M	99.5		99.5								
MX030472	FORM LINER GRID AND FIN SURFACE	SQ M	1492								1492		
MX032134	BRACED EXCAVATION	CU M	443				165			278			
MX032138	PIPE ELBOW 600MM	EACH	6	6									
MX032186	PIPE ELBOW 300MM	EACH	25	25									
MX032188	CLASS SI CONCRETE, SPECIAL	CU M	154.2	154.2									
MX032693	REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED	METER	2025.20	2025.20									
MX033109	DRILLING AND SETTING SOLDIER PILES	CU M	749.0								749.0		
MX033182	APPLY DUST SUPPRESSION AGENTS	UNIT	1125	627	352	146							
MX033183	SOIL STABILIZERS	KG	36818	13500	18134	5184							
MX033192	AGGREGATE SUBBASE	M TON	19081	18355		726							
MX033194	WHITEWASH	SQ M	24710	24710									
MX033462	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	707.60	707.60									
MX203010	SPECIAL EXCAVATION	CU M	11470		5900	5570							
MX406024	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	M TON	3419		3419								
MX406216	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	6555		6555								
MX406295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL - 19.0L (LOW ESAL)	M TON	7659	7656		3							
MX500133	FLOATING BEARINGS, FIXED-1850KN	EACH	4						4				
MX500325	FLOATING BEARINGS, GUIDED EXPANSION, 1500KN	EACH	20						8	12			
MX500335	FLOATING BEARINGS, GUIDED EXPANSION, 2000KN	EACH	4						4				
MX504002	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS, 1829MM	METER	380				380						

SHEET 12 OF 15

- (1) WB I-74 STA 152+445.837 TO STA 153+892.180
- (2) MAIN STREET STA 2+800.000 TO STA 4+157.000
- (3) MAIN STREET STA 2+402.933 TO STA 2+800.000

- (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)
BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET)
- (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)
- (7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)

TOTAL BILL OF MATERIALS

DATE 12-20-04

DRAWN BY MLS
CHECKED BY JJM