

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	108
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

* (90-11R-2;90(13,14,14-1)R-1

STORM SEWER SCHEDULES - PIPES

PIPE NO.	STATION TO STATION	U/S - D/S	STORM SEWER, CLASS A												TRENCH BACKFILL SPECIAL	CONC. COLLAR	REBAR	
			TYPE 1					TYPE 2				TY 3	TYPE 4					
			300 mm	450 mm	600 mm	675 mm	750 mm	300 mm EQ	450 mm	600 mm	750 mm	300 mm	300 mm	750 mm				
MAIN STREET																		
129	3+970.000 -- 3+970.000	175 - 174	1.8														0.3	
129a	4+001.000 -- 4+001.000	175a - 174a	1.7														1.1	
130a	4+001.000 -- 3+970.000	174a - 174								31.0							7.9	
130b	4+030.000 -- 4+001.000	176 - 174a								29.2								
131	4+030.000 -- 4+030.000	177 - 176								2.0							0.5	
131a	4+053.000 -- 4+053.000	176b - 176a								1.6							0.6	
132a	4+053.000 -- 4+030.000	176a - 176								23.0								
132b	4+097.000 -- 4+053.000	178 - 176a								44.4							8.1	
133	4+097.000 -- 4+097.000	179 - 178	1.7														0.5	
134	3+970.000 -- 3+970.000	180 - 181											14.8				3.3	
135	4+107.000 -- 4+097.000	183 - 179	10.1														3.4	
136	4+100.000 -- 4+100.000	184 - 185													17.5		4.4	
136a	4+100.000 -- 4+100.000	184a - 184	10.3														7.7	
TOTAL QUANTITIES			387.0	106.8	23.5	6.0	13.3	32.0	260.4	189.6	135.8	128.1	64.4	17.5	16.5	227.0 *	3.5	116

* = "NOT A TOTAL QUANTITY" (FOR TOTAL QUANTITY ADD SIMILAR ITEMS).

STORM SEWER SCHEDULES- FILL EXISTING STRUCTURE

FROM				TO				FILL EXISTING STORM SEWER		
STATION		OFFSET		STATION		OFFSET		762 MM	915 MM	1.2 M
LENGTH	CU M	LENGTH	CU M	LENGTH	CU M	LENGTH	CU M	LENGTH	CU M	
MAIN STREET										
3+657.844	23.846	LT	3+680.045	11.658	RT			44.6	29.3	
3+862.506	16.10	RT	3+894.236	11.98	LT	41.6	19.0			
3+894.236	11.98	LT	3+912.405	28.07	LT				24.3	27.5
3+918.211	14.93	RT	3+894.236	11.98	LT			36.0	23.7	
TOTALS							19.0		53.0	27.5
							TOTAL CUBIC METERS		99.5	

STORM SEWER SCHEDULES- ADJUSTMENT ITEMS

			INLET ADJ
STR. NO.	STATION	OFFSET	EXIST F&G
MAIN STREET			EA
182a	4+034.491	0.669 RT	1
TOTAL QUANTITIES			1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 MAIN STREET
 RAMPS J-3 & J-4



DATE 12/20/04
 DRAWN BY BRW
 CHECKED BY MJS