

\\p1n6s101101-5a.dgn 1/10/2005 8:28:22 AM

68201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	343
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\*(90-11)R-2:9013, 14, 14-1R-1

\* L1 IS THE POST CLOSEST TO THE ROADWAY EDGE OF PAVEMENT

\*\* FOR INFORMATION ONLY ITEM INCLUDED IN TEMPORARY SIGN ITEMS

## BILL OF MATERIALS - TEMPORARY SIGNING

(SHEET 4 OF 5)

LOCATION	STATION	SIGN DIMENSIONS		COMPOSITE TEMPORARY SIGN OVERLAY (SQ m)	SIGN PANEL OVERLAY (SPECIAL) (SQ m)	WOOD SIGN SUPPORT **		CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT ** (EACH)	MOUNTING		REINSTALL TEMP SIGN PANEL ASSEMBLY (EACH)	RELOCATE SIGN PANEL ASSEMBLY TYPE B (EACH)	TEMP SIGN PANEL ASSEMBLY (SQ m)	LEGEND	SIGN DETAIL	COMMENTS
		HEIGHT (mm)	WIDTH (mm)			L1 (m)	L2 (m)		HT. ABOVE E/P (m)	OFFSET FROM E/P (m)						
WB I-74 STAGE 3B																
LT	152+909	914	2550			4.3	4.3	2	1.8	4.0			2.3	← METAMORA - PEKIN → LANE ENDS 800 FEET ↓	15	PLACE ON RAMP J-4 TSPA REMOVE
RT	152+838													WEST		PLACE ON RAMP J-4 TSPA
LT	152+963	305	610										0.2	150		PLACE ON RAMP J-4 TSPA
LT	152+963	610	750										0.5	EAST		PLACE ON RAMP J-4 TSPA
LT	152+963	305	610			5.0		1	1.8	4.0			0.2	EAST		PLACE ON RAMP J-4 TSPA
LT	152+963	610	750										0.5	ILLINOIS 116		PLACE ON RAMP J-4 TSPA
LT	152+963	381	533										0.2	←		PLACE ON RAMP J-4 TSPA
LT	152+963	305	610										0.2	EAST		PLACE ON RAMP J-4 TSPA
LT	152+963	610	750										0.5	150		PLACE ON RAMP J-4 TSPA
LT	152+963	305	610			5.0		1	1.8	4.0			0.2	WEST		PLACE ON RAMP J-4 TSPA
LT	152+963	610	750										0.5	ILLINOIS 116		PLACE ON RAMP J-4 TSPA
LT	152+963	381	533										0.2	↑		PLACE ON RAMP J-4 TSPA
LT	153+165										1			EXIT 95A - NORTH MAIN ST.		REINSTALL
LT	153+165	762	1173		0.9									EXIT 95A - NORTH MAIN ST.	17	COVER "A"
LT	153+165	800	1130	0.9										EXIT 95A - NORTH MAIN ST.	26	COVER "C" WITH "B"
LT	153+190										1			CASINO →		REINSTALL AT STA. 152+905
LT	153+190	550	800	0.2										CASINO →	20	COVER "→" WITH "←"
LT	153+176										1			EXIT 94 - RIVERFRONT DR. 1/2 MILE		REINSTALL AT STA. 153+332
LT	153+289										1			EXIT 95		REINSTALL AT STA. 153+081
LT	153+338													EXIT 96 - 116 EAST METAMORA		REMOVE
LT	153+726													WEST - ILL 116 - RAMP CLOSED		REMOVE
LT	153+726													EXIT 95 - METAMORA NEXT RIGHT		REMOVE
EB I-74 STAGE 3C																
	152+206													WORK ZONE - SPEED LIMIT 55- \$XXX FINE MINIMUM		REMOVE AFTER CONC. BARRIER MED. INSTALLED IN GAP
	152+455													SPEED LIMIT 55 - 45 MINIMUM		REMOVE SPO(S) AFTER CONC. BAR. MED. INSTALLED
	153+433													WORK ZONE - SPEED LIMIT 55- \$XXX FINE MINIMUM		REMOVE AFTER CONC. BARRIER MED. INSTALLED IN GAP
	153+606													EXIT 96 - EAST WASHINGTON STREET		REMOVE SPO(S) AND CTSO
SUBTOTAL SHEET 4 OF 5				1.1	0.9	**18.6		** 4			4		5.5			

TSPA = TEMPORARY SIGN PANEL ASSEMBLY

T. I. S. SHEET 4 OF 33

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 74 (I-74)
NAME	DATE	
		TEMPORARY GUIDE SIGN DETAILS



DRAWN BY RLS  
CHECKED BY JJM

DATE 12-20-04