

... \pkins.s01101-50.dgn 1/10/2005 9:28:10 AM

08201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	344
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*(90-11)R-2;90(13, 14, 14-1)R-1

* L1 IS THE POST CLOSEST TO THE ROADWAY EDGE OF PAVEMENT

** FOR INFORMATION ONLY
ITEM INCLUDED IN TEMPORARY SIGN ITEMS

BILL OF MATERIALS - TEMPORARY SIGNING

(SHEET 5 OF 5)

LOCATION	STATION	SIGN DIMENSIONS		COMPOSITE TEMPORARY SIGN OVERLAY (SQ m)	SIGN PANEL OVERLAY (SPECIAL) (SQ m)	WOOD SIGN SUPPORT **		CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT ** (EACH)	MOUNTING		REINSTALL TEMP SIGN PANEL ASSEMBLY (EACH)	RELOCATE SIGN PANEL ASSEMBLY TYPE B (EACH)	TEMP SIGN PANEL ASSEMBLY (SQ m)	LEGEND	SIGN DETAIL	COMMENTS
		HEIGHT (mm)	WIDTH (mm)			L1 (m)	L2 (m)		HT. ABOVE E/P (m)	OFFSET FROM E/P (m)						
WB I-74 STAGE 3C																
LT	152+243													RIVERFRONT DR. - DOWNTOWN PEORIA		REMOVE CTSO TO REVEAL " ↓ EXIT ONLY ↓ "
LT	152+243													LANE ENDS 800 FEET		REMOVE SPO
LT	152+267									1				40 NORTH - RIVERFRONT DR.		REINSTALL AT STA. 152+309
LT	152+446													DOWNTOWN PEORIA VIA MICHEL BRIDGE		REMOVE CTSO TO REVEAL " ↓ EXIT ↓ ONLY "
RT	152+629									1				PEORIA CIVIC CENTER		REINSTALL AT STA. 152+709
RT	152+838													40 NORTH - RIVERFRONT DR.		REMOVE
RT	152+838													I-74 WEST - KEEP LEFT		REMOVE
RT	152+892									1				WORK ZONE - SPEED LIMIT 55 -XXX FINE MINIMUM		REINSTALL AT LT STA. 152+892
LT	152+905													CASINO ←		REMOVE
RT	153+081													EXIT 95 LT ↗		REMOVE
LT	153+154									1				NORTH MAIN ST.		REINSTALL AT STA. 153+441
LT	153+175									1				RIVERFRONT DR. 1/2 MILE		REINSTALL AT STA. 153+163
LT	153+449													CASINO →		REMOVE
SUBTOTAL SHEET 5 OF 5											5					

TSPA = TEMPORARY SIGN PANEL ASSEMBLY

T. I. S. SHEET 5 OF 33

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)
TEMPORARY GUIDE SIGN DETAILS



DRAWN BY RLS
CHECKED BY JJM
DATE 12-20-04