



| | | | | |
|-----------------------|---------|---------------------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 74 | * | TAZEWELL | 1366 | 930 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 4 | | ILLINOIS FED. AID PROJECT | | |

• (90-111R-2;90113,14,14-11R-1

BENCH MARKS

| BENCHMARK | ELEVATION | DESCRIPTION |
|-----------|-----------|---|
| ID0T19 | 143.777 | Chiseled "L" on Southeast Corner of Northwest Crashwall of Westbound Bridge, Sta. 153+825 Westbound, 4 m Right |
| FASTBM1 | 154.780 | Chiseled square on East side Headwall, Sta.154+295, Westbound, 42 m Right |
| ID0T17 | 158.783 | Chiseled square on Southeast steel base pad of Exit 96 Sign Truss, I-74 Ramp to IL 8, Sta. 154+300 Westbound, 5 m Right |
| FASTBM2 | 164.524 | Northeast Bolt In Light Pole Base, # K-10(24), Sta. 154+486 Westbound, 25 m Right |
| FASTBM3 | 168.708 | Southeast Bolt Anchor for Sign Base Sta. 154+650, Westbound, 20 m Left |
| FASTBM4 | 176.715 | Northeast Bolt of Sign Base, Sta. 154+895, Westbound, 21 m Left |

01/07/2005 05:45:56 PM
g:\gdgfa\5589-74\dwg\control\11\1103-6a.dgn



| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

SHEET 1 OF 1

ALL STATIONS INDICATED ARE WESTBOUND STATIONING UNLESS OTHERWISE NOTED.

ILLINOIS DEPARTMENT OF TRANSPORTATION

**ALIGNMENTS
TIES & BENCH MARKS**

DRAWN BY
CHECKED BY

DATE 01/07/2005

CONTRACT 11: PLAN SET 2 OF 4 FINAL PLANS 01/05