

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	1269
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 190-111R-2;90(13,14,14-1)R-1		CONTRACT NO. 68201		

**BILL OF MATERIALS - GROUND MOUNTED SIGNS  
B. PROPOSED**

SIGN PANEL NO.	ROADWAY	STATION	DESCRIPTION	SIGN PANEL TYPE 2		SIGN PANEL TYPE 3		NO. OF POSTS	POST SIZE	WOOD POST (m)	POST SPACING C-C (mm)	SIGN POST LENGTH (m)				STUB POST LENGTH EACH (m)	STRUCTURAL STEEL SUPPORT-BREAKAWAY (1) (KG)	FOUN-DATION CONCRETE (CU m)	FOUN-DATION REIN-FORCEMENT (2) (KG)	FUSE PLATE BOLT SIZE	SIGN PANEL OVERLAY (SQ. m)	SIGN DIMENSIONS (m)					REMARKS / WORK TIMING
				PANEL SIZE (mm x mm)	TOTAL AREA (SQ. m)	PANEL SIZE (mm x mm)	TOTAL AREA (SQ. m)					L1	L2	L3	L4							A	B	C*	D**	E	
6-18	I-74 WB	155+025	HOSPITAL DESTINATION SIGN			7050 x 3048	21.49	3	W250x39		2468	6.02	6.62	7.16		0.91	878.7	2.85	156	M22x65		7.05	3.05	2.1	4.5	4.11	FOR STAGE 3C
6-16	I-74 WB	155+315	EXIT 96 EAST WASHINGTON ST 1/2 MILE			6150 x 4267	26.24	4	W250x39		1538	6.96	7.28	7.57	8.06	0.91	1306.9	3.80	208	M24x70		6.15	4.27	2.1	4.5	3.79	FOR STAGE 3C
6-21	I-74 WB	155+500	EAST WASHINGTON ST 3/4 NORTH MAIN ST 1 1/2 RIVERFRONT DR 2 1/4			6750 x 2134	14.40	3	W250x33		2362	5.84	5.01	4.23		0.91	587.7	2.73	147	M16x50		6.75	2.13	2.52	7.2	3.70	FOR STAGE 3C
5-14	NORTH MAIN ST	2+446	I-74 WEST / PEORIA / LEFT			2400 x 1372	3.29	2	W150x22		1440	4.21	4.45			0.76	224.0	1.06	82	M12x45		2.40	1.37	2.6	3.0	3.08	POST STAGE 3C
5-15	NORTH MAIN ST	2+490	I-74 EAST / BLOOMINGTON / AHEAD I-74 WEST / PEORIA / RIGHT			3000 x 2743	8.23	2	W150x22		1800	5.72	5.20			0.76	273.7	1.06	82	M20x50		3.00	2.74	2.1	9.0	2.98	POST STAGE 3C
	I-74 WB	155+750	ILLINOIS CENTRAL COLLEGE / USE EXIT 95																		1.5						PANEL OVERLAY FOR STAGE 3C
	I-74 WB	155+875	EASTSIDE SPORTS COMPLEX / EXIT 96					2	W150x22		2834	4.99	4.08			0.76	233.0	1.06	82	M16x50		4.72	1.98	2.44	9.0	3.01	RELOCATED SIGN PANEL; REINSTALL PANEL ON NEW FOUNDATION FOR STAGE 3C
6-26	I-74 WB	156+000	EXIT 96 EAST WASHINGTON ST 1 MILE			6150 x 4267	26.24	3	W360x45		2152	7.76	7.04	6.37		0.91	1075.5	4.29	183	M24x70		6.15	4.27	3.58	10.7	3.49	FOR STAGE 3C
	I-74 WB	156+485	EAST PEORIA / NEXT 3 EXITS																		1.0						PANEL OVERLAY FOR STAGE 3C
	I-74 WB	157+366	BRADLEY UNIVERSITY / EXIT 91																		1.5						PANEL OVERLAY FOR STAGE 3A
TOTAL THIS SHEET							0.00				0.0						4579.5	16.85	940		4.0						

**BILL OF MATERIALS - GROUND MOUNTED SIGNS  
B. TOTAL PROPOSED**

SIGNING PLAN SHEET NO.	SIGN PANEL TYPE 2 TOTAL AREA (SQ. m)	SIGN PANEL TYPE 3 TOTAL AREA (SQ. m)	WOOD POST (m)	STRUCTURAL STEEL SUPPORT-BREAKAWAY (1) (KG)	FOUN-DATION CONCRETE (CU m)	FOUN-DATION REIN-FORCEMENT (2) (KG)	SIGN PANEL OVERLAY (SQ. m)
16	2.19	108.38	37.5	4264.8	16.58	1025	0.0
17	0.00	99.90	0.0	4579.5	16.85	940	4.0
TOTAL	2.19	208.28	37.5	8844.3	33.43	1965	4.0

SIGNING SHEET 17 OF 74

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  SIGNING PLAN BILL OF MATERIALS- GROUND MOUNTED SIGNS (PROPOSED)  SCALE 1:500 DATE 12/21/2004	DRAWN BY MEG CHECKED BY BCG
NAME	DATE		



\\sbs\cadd\110221\plan\mehrad\contract\11ac1116-7b.dgn 12/21/2004