

SUMMARY OF QUANTITIES

P.A.P. SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38-2)RS	MCDONOUGH	66	6
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ALPINE	FED. AID PROJECT	

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM			URBAN 80% FED/20% STATE I 000	RURAL 80% FED/20% STATE I 000			
20201100	GRADING EXISTING SHOULDER	UNIT	10	10	0			
20400800	FURNISHED EXCAVATION	CU YD	117	49	68			
21400100	GRADING AND SHAPING DITCHES	FOOT	2356	1557	799			
25000210	SEEDING, CLASS 2A	ACRE	0.27	0.17	0.1			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25	16	9			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25	16	9			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25	16	9			
25002300	TEMPORARY SEEDING	ACRE	0.54	0.34	0.2			
25100115	MULCH, METHOD 2	ACRE	0.27	0.17	0.1			
28000400	PERIMETER EROSION BARRIER	FOOT	1012	258	754			
28000500	INLET AND PIPE PROTECTION	EACH	4	1	3			
28001000	AGGREGATE (EROSION CONTROL)	TON	35	31	4			
28100825	STONE DUMPED RIPRAP, CLASS B3	TON	619	196	423			
28200200	FILTER FABRIC	SQ YD	1237	392	845			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	13	27			
40600300	AGGREGATE (PRIME COAT)	TON	243	90	153			
40600895	CONSTRUCTING TEST STRIP	EACH	2	0.7	1.3			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2665	1809	856			
40600990	TEMPORARY RAMP	SQ YD	3182	1613	1569			
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	208	38	170			