

# SUMMARY OF QUANTITIES

F. A. P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38-2)RS	MCDONOUGH	66	7
STA.		TO STA.		
FED. ROAD DIST. NO. 6		BALANCE	FED. AID PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 80% FED/20% STATE I 000	RURAL 80% FED/20% STATE I 000			
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	SQ YD	500		500			
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1321	203	1118			
44000012	BITUMINOUS SURFACE REMOVAL 4 1/2"	SQ YD	71774	22935	48839			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1283	317	966			
54200649	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	80		80			
54215550	METAL END SECTIONS 15"	EACH	1	1				
54215559	METAL END SECTIONS 24"	EACH	3	1	2			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	700	626	74			
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2				
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2				
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	3	1			
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1251	1144	107			
63500105	DELINEATORS	EACH	11	1	10			
63500120	DELINEATOR REMOVAL	EACH	11	1	10			
* 66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	2	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	0.7	1.3			
67100100	MOBILIZATION	L SUM	1	0.35	0.65			

\* SPECIALTY ITEMS