

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38-2)RS	MCDONOUGH	66	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**BITUMINOUS RESURFACING**

LOCATION	AREA	BIT SURF REMOVAL BT JT	BIT SURF REMOVAL ( 4 1/2")	POLY BCSC SUPERPAVE MIX D, N50 (2")	POLY BCBC SUPERPAVE IL 19.0, N50 (2.5")
	SQ FT	SQ YD	SQ YD	TON	TON
<b>CROSSOVERS</b>					
STA 90+50	1591.3		176.8	19.8	24.8
STA 96+00	1719.5		191.1	21.4	26.8
STA 112+00	2397.6		266.4	29.8	37.3
STA 128+00	2397.0		266.3	29.8	37.3
STA 138+00	1669.6		185.5	20.8	26.0
<b>MEDIAN</b>					
STA 61+00 - 61+60	630.0	70.0		7.8	9.8
STA 61+60 - 78+82.04	25862.5		2873.6	321.9	405.2
<b>TURN LANES</b>					
RT. STA. 86+60.64 - 91+08.71	4109.2	27.3	440.7	51.1	63.9
RT. STA 91+08.71 - 96+92.23	5272.7		585.9	65.6	82.0
LT. STA 95+00 - 101+43.60	5055.5		561.7	63.0	78.6
LT. STA 95+39.04 - 100+95.88	4962.3		551.4	61.8	78.2
RT. STA 133+50.18 - 139+00	4773.2		530.4	59.4	74.3
<b>TOTALS</b>		<b>97.3</b>	<b>6629.8</b>	<b>752.2</b>	<b>944.2</b>

APPLICATION RATE = 112 LB/SQ YD/IN

**BITUMINOUS RESURFACING - MAINLINE**

LOCATION	AREA	BIT SURF REMOVAL BUTT JT	BIT SURF REMOVAL ( 4 1/2")	POLY BCSC SUPERPAVE MIX D, N50 (2")	POLY BCBC SUPERPAVE IL 19.0, N50 (2.5")
	SQ FT	SQ YD	SQ YD	TON	TON
<b>SOUTH BOUND</b>					
STA 61+00 - 61+60	1500.0	166.7		18.7	23.3
STA 61+60 - 83+55.06	53722.9		5969.2	668.6	835.7
STA 83+55.06 - 84+15.06	1440.0	160.0		17.9	22.4
<b>BRIDGE OMISSION</b>					
STA 86+85.40 - 87+45.40	1440.0	160.0		17.9	22.4
STA 87+45.40 - 104+42.87	127139.3		14126.6	1582.2	1977.7
STA 140+42.87 - 141+02.87	1440.0	160.0		17.9	22.4
<b>NORTH BOUND</b>					
STA 61+00 - 61+60	1470.0	163.3		18.3	22.9
STA 61+60 - 83+30.30	53172.4		5908.0	661.7	827.1
STA. 83+30.30 - 83+90.30	1470.0	163.3		18.3	22.9
<b>BRIDGE OMISSION</b>					
STA 86+60.64 - 87+20.64	1440.0	160.0		17.9	22.4
STA 87+20.64 - 140+42.87	127733.5		14192.6	1589.6	1987.0
STA 140+42.87 - 141+02.87	1440.0	160.0		17.9	22.4
<b>TOTALS</b>		<b>1293.3</b>	<b>40196.4</b>	<b>4646.9</b>	<b>5808.6</b>

APPLICATION RATE = 112 LB/SQ YD/IN

PLOT DATE = 3/23/2006  
 PLOT SCALE = 1/8"=1'-0"  
 REFERENCE = WREF

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_