

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	138-21RS	MCDONOUGH	66	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**BITUMINOUS RESURFACING - SIDEROADS**

LOCATION	AREA SHOULDER	AREA MAINLINE	BIT SURF REMOVAL BUTT JT	BIT SURF REMOVAL 1/2" MAINLINE	BIT SURF REMOVAL 2"	*BIT SURF REMOVAL VAR DEPTH MAINLINE	*BIT SURF REMOVAL VAR DEPTH SHOULDER	POLY BCSC SUPERPAVE MIX D, N50 (2")	POLY BCBC SUPERPAVE IL 19.0, N50 (2.5")	BCSC SUPERPAVE IL 9.5L LE (2")	BCBC SUPERPAVE IL 19.0L LE (2.5")	INCIDENTAL BITUMINOUS SURFACE (2")
	SQ FT	SQ FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON		TON
NEW BURLINGTON RD.	388.7	3074.6	182.5		202.4					4.9		38.3
DOG POUND DRIVE	1130.6	7861.6	76.1	500.0		297.4	125.6	97.8	122.3	14.0	17.6	
HURST DRIVE		2253.1	112.9		137.5							28.0
TOWER RD.	2513.4	8294.1	133.9		980.3					31.2		141.3
<b>TOTALS</b>			<b>505.4</b>	<b>500.0</b>	<b>1320.2</b>	<b>297.4</b>	<b>125.6</b>	<b>97.8</b>	<b>122.3</b>	<b>50.1</b>	<b>17.6</b>	<b>207.6</b>

APPLICATION RATE = 112 LB/SQ YD/IN

\*PAID AS BITUMINOUS SURFACE REMOVAL 4-1/2"

**GUARDRAIL REMOVAL**

LOCATION	SPBGR REMOVAL
	FOOT
NB RT. STA. 81+44.08 - 84+35.83	291.8
NB LT. STA. 82+84.17 - 84+50.40	166.2
SB LT. STA. 83+58.44 - 84+60.96	102.5
SB RT STA 84+18.88 - 84+46.40	27.5
NB RT. STA. 86+14.74 - 87+17.26	102.5
SB RT. STA. 86+25.30 - 87+91.53	166.2
NB LT STA 86+29.30 - 86+56.82	27.5
SB LT. STA. 86+39.86 - 90+06.62	366.8
<b>TOTAL</b>	<b>1251.0</b>

**GUARDRAIL**

LOCATION	TBT, TYPE 1 SPECIAL (TANGENT)	SPBGR, TYPE A	TBT, TYPE 5	TBT, TYPE 6B	TBT, TYPE 2	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
	EACH	FOOT	EACH	EACH	EACH	EACH	EACH
NB LT. STA. 81+98.44 - 84+44.69	1	150.0		1		4	1
NB RT. STA. 82+52.15 - 84+35.90	1	87.5		1		3	1
NB RT. STA. 86+19.69 - 86+57.94		12.5	1		1	1	
SB LT. STA. 84+17.70 - 84+55.95		12.5	1		1	1	
SB RT. STA. 86+30.96 - 88+77.21	1	150.0		1		4	1
SB LT. STA. 86+39.84 - 90+23.59	1	287.5		1		5	1
<b>TOTAL</b>	<b>4</b>	<b>700.0</b>	<b>2</b>	<b>4</b>	<b>2</b>	<b>18</b>	<b>4</b>

**PERMANENT SURVEY MARKERS TYPE II**

LOCATION	EACH
STA. 65+00	1
STA. 75+00	1
STA. 96+11.02	1
<b>TOTAL</b>	<b>3</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

PLOT DATE: 3/23/2006  
 FILE NAME: c:\p\proj\68334\sheet.dgn  
 PLOT SCALE: 1/8"=1'-0"  
 REFERENCE: 0REF