

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CHAMPAIGN	21	15

CONTRACT NO. 70470
 * F.A.P. RTE. 836 & F.A.S. RTE. 516
 ** D-5 CONTRACT MAINT 2005-13

BITUMINOUS SURFACE REMOVAL (SPECIAL) - 44000025
OGDEN (LOCATION #1)

<u>STATION</u>	<u>ITEM</u>	<u>AREA</u> (sq. yd)
327+50.00 RT	GAS STATION ENT.	220.0
331+29.00 LT	NORTH ST	144.0
332+20.00 RT	N. PARK ENT.	34.5
334+76.00 LT	KYLE ST	162.0
335+80.00 LT	MAILBOX	5.0
336+48.00 LT	MAILBOX	5.0
336+75.00 RT	S. PARK ENT.	30.0
337+00.00 LT	PRIV. ENT.	12.0
338+35.12 RT	MAIN ST	240.2
338+35.12 LT	MAIN ST	312.3
<u>TOTAL</u>		1165.0 (sq. yd.)

INCIDENTAL BIT SURF - 40800040
OGDEN (LOCATION #1)

<u>STATION</u>	<u>ITEM</u>	<u>TONS</u>
327+50.00 RT	GAS STATION ENT.	18.6
331+29.00 LT	NORTH ST	12.1
332+20.00 RT	N. PARK ENT.	2.9
334+76.00 LT	KYLE ST	13.6
335+80.00 LT	MAILBOX	0.4
336+48.00 LT	MAILBOX	0.4
336+75.00 RT	S. PARK ENT.	2.5
337+00.00 LT	PRIV. ENT.	1.0
338+35.12 RT	MAIN ST	20.3
338+35.12 LT	MAIN ST	26.4
<u>OGDEN TOTAL</u>		98.0 (TONS)

ST. JOSEPH (LOCATION #2)

<u>STATION</u>	<u>ITEM</u>	<u>TONS</u>
64+02.00 T	GRAND AVE. TURN LANE	33.8
<u>ST. JOSPEH TOTAL</u>		34.0 (TONS)
<u>TOTAL</u>		132.0 (TONS)

PCC SURF REM BUTT JT - 40600985
ST. JOSEPH (LOCATION #2)

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>LENGTH</u> (ft)	<u>WIDTH</u> (ft)	<u>AREA</u> (sq. yd)
62+52 LT		65+52 LT	300	12	400.0
<u>TOTAL</u>					400.0 (sq. yd.)