

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CHAMPAIGN	21	16

CONTRACT NO. 70470
 * F.A.P. RTE. 836 & F.A.S. RTE. 516
 ** D-5 CONTRACT MAINT 2005-13

THERMOPLASTIC PAVEMENT MARKING LINE 4" - 78000200 OGDEN (LOCATION #1)

STATION	TO	STATION	ITEM	FEET
326+54.00		338+99.00	SKIP DASH CENTERLINE	311.3
326+54.00		338+99.00	2 EDGE LINES	2490.0
OGDEN TOTAL				2801.3

THERMOPLASTIC PAVEMENT MARKING LINE 4" - 78000200 ST. JOSEPH (LOCATION #2)

STATION	TO	STATION	ITEM	FEET
51+19.50		66+32.00	2 EDGE LINES	3025.0
51+19.50		66+32.00	2 SOLID CENTERLINES	2115.8
58+52.00		61+25.30	NORTH PAINTED MEDIAN	1093.2
63+60.00		65+41.33	SOUTH PAINTED MEDIAN	725.2
ST. JOSEPH TOTAL				6959.2
CONTRACT TOTAL				9760.5

PAINT PAVEMENT MARKING LINE 4" - 78001110 ST. JOSEPH (LOCATION #2)

STATION	TO	STATION	ITEM	FEET
29+32.00		48+80.50	2 EDGE LINES	3897.0
29+32.00		48+80.50	1 SOLID CENTERLINES	1948.5
29+32.00		48+80.50	1 SKIP DASH CENTERLINE	487.1
ST. JOSEPH TOTAL				6336.2
CONTRACT TOTAL				6336.2