

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		MACQUEIN	14	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• 10Z (RS-1); (V,T) RS-2; S(RS-4)

BITUMINOUS WIDENING / SHOULDERS & AGGREGATE SHOULDERS

LOCATION	LENGTH	BIT PAY WIDTH	BITUMINOUS SHOULDERS SUPER., 8"	BIT. CONC. BSE. CSE. WID. SUPER., 10"	EXCAVATING AND GRADING EX SHLDS	GRADING AND SHAPING SHOULDERS	EARTH EXCAVATION (WIDENING)	AGG WIDTH	AGGREGATE SHOULDERS	AGGREGATE SHOULDERS (SPECIAL)	REMOVE & REINSTALL SPBCR
	FOOT	FOOT	SQ YD	SQ YD	UNIT	UNIT	UNIT	FOOT	TON	TON	FOOT
PART "A" - CITY											
LT STA 131+14.00 TO LT STA 134+40.00	326.00	8.0	289.9	-	3.26	-	-	3.0	15.47	-	-
LT STA 134+40.00 TO LT STA 140+80.00	640.00	8.0	568.9	-	6.40	6.4	-	3.0	30.37	-	640
LT STA 140+80.00 TO LT STA 141+14.00	34.00	8.0 TO 3.0	20.7	-	0.34	-	-	3.0	1.61	-	-
LT STA 141+14.00 TO LT STA 143+00.00	186.00	3.0	62.0	-	1.86	-	-	3.0	8.83	-	-
LT STA 143+00.00 TO LT STA 148+62.00 (GUTTER)	562.00	3.0	187.3	-	5.62	-	-	-	-	-	-
LT STA 148+62.00 TO LT STA 149+12.00	50.00	3.0 TO 1.0	11.1	-	0.50	-	-	3.0	2.37	-	-
LT STA 149+12.00 TO LT STA 158+68.00	956.00	1.2	127.5	-	9.56	-	-	3.0	45.37	-	-
RT STA 130+84.00 TO RT STA 142+55.00	1171.00	3.0	390.3	-	11.71	-	-	5.0	92.61	-	-
RT STA 142+55.00 TO RT STA 143+05.00	50.00	3.0 TO 1.0	11.1	-	0.50	-	-	3.0	2.37	-	-
RT STA 143+05.00 TO RT STA 158+68.00	1563.00	1.2	208.4	-	15.63	-	-	3.0	74.17	-	-
SUB-TOTAL =			1877.3	0.0	55.4	6.4	0.0	-	273.2	0.0	640.0
PART "A" - RURAL											
LT STA 158+68.00 TO LT STA 199+50.00	4082.00	1.2	544.3	-	40.82	-	-	3.0	193.71	-	-
LT STA 199+50.00 TO LT STA 200+00.00	50.00	1.0 TO 3.0	11.1	-	0.50	-	-	3.0	2.37	-	-
LT STA 200+00.00 TO LT STA 203+25.00 (GUTTER)	325.00	3.0	108.3	-	3.25	-	-	-	-	-	-
LT STA 203+25.00 TO LT STA 204+86.00	161.00	3.0	53.7	-	1.61	-	-	3.0	7.64	-	-
LT STA 204+86.00 TO LT STA 208+00.00 (GUTTER)	314.00	3.0	104.7	-	3.14	-	-	-	-	-	-
LT STA 208+00.00 TO LT STA 208+50.00	50.00	3.0 TO 1.0	11.1	-	0.50	-	-	3.0	2.37	-	-
LT STA 208+50.00 TO LT STA 217+18.85	868.85	1.2	115.8	-	8.69	-	-	3.0	41.23	-	-
LT STA 217+18.85 TO LT STA 217+68.85	50.00	1.0 TO 8.0	25.0	-	0.50	-	-	3.0	2.37	-	-
LT STA 217+68.85 TO LT STA 220+86.93	318.08	-	-	-	-	-	-	2.0	-	10.06	-
LT STA 220+86.93 TO LT STA 225+06.26 - BRIDGE OMISSION											
LT STA 225+06.26 TO LT STA 228+07.24	300.98	-	-	-	-	-	-	2.0	-	9.52	-
LT STA 228+07.24 TO LT STA 228+57.24	50.00	8.0 TO 3.0	30.6	-	0.50	-	-	5.0 TO 3.0	3.16	-	-
LT STA 228+57.24 TO LT STA 233+14.00	456.76	3.0	152.3	-	4.57	-	-	3.0	21.67	-	-
LT STA 233+14.00 TO LT STA 245+50.00 (GUTTER)	1236.00	3.0	412.0	-	12.36	-	-	-	-	-	-
LT STA 245+50.00 TO LT STA 246+00.00	50.00	3.0 TO 1.0	11.1	-	0.50	-	-	3.0	2.37	-	-
LT STA 246+00.00 TO LT STA 442+85.00	19685.00	1.2	2624.7	-	196.85	-	-	3.0	934.13	-	-
LT STA 442+85.00 TO LT STA 446+25.50	340.50	5.2	-	196.7	-	-	3.41	-	-	-	-
LT STA 446+25.50 TO LT STA 447+91.50 - BRIDGE OMISSION											
LT STA 447+91.50 TO LT STA 450+70.81	279.31	5.2	-	161.4	-	-	2.79	-	-	-	-
LT STA 450+70.81 TO LT STA 450+94.81	24.00	5.2 TO 1.2	-	8.5	-	-	0.24	-	-	-	-
LT STA 450+94.81 TO LT STA 478+00.00 (BK)	2705.19	1.2	360.7	-	27.05	-	-	3.0	128.37	-	-
RT STA 158+68.00 TO RT STA 217+18.85	7413.85	1.2	988.5	-	74.14	-	-	3.0	351.81	-	-
RT STA 217+18.85 TO RT STA 217+68.85	50.00	1.0 TO 8.0	25.0	-	0.50	-	-	3.0	2.37	-	-
RT STA 217+68.85 TO RT STA 220+97.57	328.72	-	-	-	-	-	-	2.0	-	-	-
RT STA 220+97.57 TO RT STA 225+16.90 - BRIDGE OMISSION											
RT STA 225+16.90 TO RT STA 228+07.24	290.34	-	-	-	-	-	-	2.0	-	-	-
RT STA 228+07.24 TO RT STA 228+57.24	50.00	8.0 TO 3.0	30.6	-	0.50	-	-	3.0	2.37	-	-
RT STA 228+57.24 TO RT STA 233+14.00	456.76	3.0	152.3	-	4.57	-	-	3.0	21.67	-	-
RT STA 233+14.00 TO RT STA 244+85.00 (GUTTER)	1171.00	3.0	390.3	-	11.71	-	-	-	-	-	-
RT STA 244+85.00 TO RT STA 245+15.00	30.00	3.0	10.0	-	0.30	-	-	3.0	1.42	-	-

CONTINUED ON NEXT PAGE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY