

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		MACOUPIN	73	19
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• 10Z (RS-1); (V,T) RS-2; SIRS-4)

PAVEMENT MARKING AND REFLECTIVE MARKERS

LOCATION	PAINT LINE 5"	PAINT LINE 5"	PAINT LINE 5"	PREF PLAST LINE 5"	PREF PLAST LINE 5"	PREF PLAST LINE 5"	PREF PLAST LINE 6"	PREF PLAST LINE 8"	PREF PLAST LINE 12"	PREF PLASTIC 24"	PREF PLASTIC LETTERS & SYMBOLS	TEMPORARY PAV'T MK LINE 5"	SHORT-TERM PAV'T MK	WORK ZONE PAV'T MK REMOVAL	RAISED REFLECTIVE PAV'T MARKER	RAISED REFLECTIVE PAV'T MARKER
	WHITE EDGE SOLID	YELLOW NO PASSING	YELLOW SKIP-DASH	WHITE	WHITE DIAGONALS	YELLOW SOLID	WHITE SOLID	WHITE ISLAND CORE	WHITE ISLAND	WHITE STOP BAR	RAILROAD					
	feet	feet	feet	feet	feet	feet	feet	feet	feet	feet	sq. feet	feet	feet	sq. feet	each	each
STA 98+45.93 TO STA 127+23.38	0	0	0	5,249	330	5,176	257	0	20	69	0	5,176	690	288	36	36
STA EQN STA 127+23.28 (BK) =	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 0+00.00 (AH)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 0+00 TO STA 7+72.45	0	0	0	1,273	0	1,316	0	0	40	0	0	1,316	192	80	10	10
STA EQN STA 5+86.59 (IL 4/IL 108) =	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 129+96.00 (IL 4)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 129+96.00 TO STA 158+68	4,536	0	570	1,335	0	1,150	0	220	82	32	0	1,720	696	290	46	46
URBAN SUBTOTAL	4,536	0	570	7,857	330	7,642	257	220	142	101	0	8,212	1,578	658	92	92
STA 158+68 TO STA 220+92.25	12,448	0	1,560	0	0	0	0	0	0	0	0	1,560	1,500	625	78	78
BRIDGE OMISSION STA 220+92.25	840	0	105	0	0	0	0	0	0	0	0	105	0	0	0	0
TO STA 225+11.58	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 225+11.58 TO STA 446+45.00	44,268	0	5,540	0	0	0	0	0	0	0	0	5,540	5,316	2,215	277	277
PROJECT OMISSION STA 446+45.00	240	0	30	0	0	0	0	0	0	0	0	30	0	0	0	0
TO STA 447+63.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 447+63.00 TO STA 478+00.00	6,074	0	760	0	0	0	0	0	0	0	0	760	732	305	38	38
STA EQN STA 478+00.00 (BK) =	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 259+79.19 (AH)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 259+79.19 TO STA 201+90.00	11,578	0	1,450	0	0	0	0	0	0	0	**12	1,450	1,392	580	73	73
RAILROAD OMISSION STA 201+90.00	0	0	0	0	0	0	0	0	0	0	**24	0	0	0	0	0
TO STA 202+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
STA 202+00.00 TO STA 38+00.00	32,800	0	4,100	0	0	0	0	0	0	0	**12	4,100	3,936	1,640	205	205
*STA 129+96.00 TO STA 38+00.00 (VARIOUS LOCATIONS)		29,040														
RURAL SUBTOTAL	108,248	29,040	13,545	0	0	0	0	0	0	48	122.4	13,545	12,876	5,365	671	671
TOTAL	112,784	29,040	14,115	7,857	330	7,642	257	220	142	149	122.4	21,757	14,454	6,023	763	763
	155,939			15,829												

** MARKINGS ARE FOR RAILROAD CROSSING

PLOT DATE = 2/27/2005
 FILE NAME = c:\p\1004337\1004337.dgn
 PLOT SCALE = 100.4337 / IN.
 REFERENCE = #REF*

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY