

F.A	SECTION	COUNTY	TOTAL	SHEET
RTE.			SHEET	NO.
1645	150RS	SANGAMON	28	7
STA.		TO STA.		
FED.ROAD DIST.NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 72876

PAINT PAVEMENT MARKING - LINE 5"	
LOCATION	TOTAL (FT)
<u>EDGE LINE - WHITE</u> LT STA 57+25 - LT STA 186+15.09 RT STA 57+25 - RT STA 186+15.09	12,890.0 12,890.0
<u>SKIP- DASH - YELLOW</u> STA 57+ 25 - STA 186+15.09	3,223.0
<u>NO PASSING ZONE - YELLOW</u> STA 78+52 - STA 79+52 STA 89+00 - STA 96+50 STA 96+50 - STA 100+60 STA 116+55 - STA 128+84 STA 144+50 - STA 158+29 STA 181+72 - STA 183+87	100.0 750.0 410.0 1,229.0 1,379.0 215.0
<u>LEFT-TURN LANE DBL YELLOW</u> STA 198+04.24 - STA 199+24.84 STA 31+56.74 - STA 32+09	173.0 173.0
<b>TOTAL</b>	<b>33,432.0</b>

STA EQU 199+24.84 BK=31+56.74 AH

PAINT PAVEMENT MARKING - LINE 6"	
LOCATION	TOTAL (FT)
<u>LEFT-TURN LANE - WHITE</u> STA 198+04.25 - STA 32+09	173.0
<b>TOTAL</b>	<b>173.0</b>

PREFORMED PLASTIC PAVEMENT MARKING- LETTERS SYMBOLS	
LOCATION	TOTAL (SQ FT)
<u>LEFT-TURN LANE - WHITE</u> STA 198+04.25 - STA 32+09 (3 LT-TURN ARROWS)	46.8
<b>TOTAL</b>	<b>46.8</b>

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES