

F.A RTE.	SECTION	COUNTY	TOTAL SHEET	SHEET NO.
1645	150RS	SANGAMON	28	8
STA.		TO STA.		
FED.ROAD DIST.NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 72876

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C N50	
LOCATION	TOTAL (TONS)
<u>MAINLINE</u> STA.57+25 - STA.186+15.09	3,850.0
<u>PORTABLE SCALE TURNOUT</u> LT STA.59+00 - LT STA.66+95 LT STA.67+45 - LT STA.75+40	158.5 158.5
TOTAL	4,167.0

AGGREGATE BASE COURSE TY. B 12"	
LOCATION	TOTAL (SQYD)
LT-TURN LANE STA.198+04.25	230.5
TOTAL	230.5

BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90 - 13"	
LOCATION	TOTAL (SQYD)
LT-TURN LANE STA 198+04.25 - STA 32+09	230.5
TOTAL	230.5

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX D N90	
LOCATION	TOTAL (TONS)
<u>LEFT-TURN LANE</u> STA 198+04.25 - STA 32+09	26.0
TOTAL	26.0

PREPARATION OF BASE	
LOCATION	TOTAL (SQ YD)
<u>CE, PE, & MAILBOX TURNOUTS</u> CE STA 89+30 RT MB STA 89+70 LT COMB PE& MB STA 96+50 LT MB STA 102+77 LT PE STA 102+63 RT COMB PE & MB STA 143 +11 LT SIDEROAD STA 157+04 LT MB STA 183+71 LT PE STA 183+87 RT	66.0 40.0 54.0 40.0 9.0 54.0 33.0 55.0 10.0
TOTAL	361.0

INCIDENTAL BITUMINOUS SURFACING	
LOCATION	TOTAL (TONS)
<u>CE, PE, & MAILBOX TURNOUTS</u> CE STA 89+30 RT MB STA 89+70 LT COMB PE& MB STA 96+50 LT MB STA 102+77 LT PE STA 102+63 RT COMB PE & MB STA 143 +11 LT SIDEROAD STA 157+04 LT MB STA 183+71 LT PE STA 183+87 RT	7.3 4.5 6.0 4.5 1.0 6.0 3.7 6.2 1.1
TOTAL	40.3

PAVEMENT REMOVAL	
LOCATION	TOTAL (SQYD)
<u>LT-TURN LANE</u> STA 198+04.25 - STA 32+09	230.5
TOTAL	230.5

BITUMINOUS SURFACE REMOVAL - 1 3/4"	
LOCATION	TOTAL (SQYD)
<u>MAINLINE</u> STA.57+25 - STA.186+15.09	34,374.0
<u>PORTABLE SCALE TURNOUT</u> LT STA.59+00 - LT STA.66+95 LT STA.67+45 - LT STA.75+40	1,413.5 1,413.5
<u>CE, PE, & MAILBOX TURNOUTS</u> CE STA 89+30 RT MB STA 89+70 LT COMB PE& MB STA 96+50 LT MB STA 102+77 LT PE STA 102+63 RT COMB PE & MB STA 143 +11 LT SIDEROAD STA 157+04 LT MB STA 183+71 LT PE STA 183+87 RT	66.0 40.0 54.0 40.0 9.0 54.0 33.0 55.0 10.0
TOTAL	37,562.0

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES