CONTRACT NO. 72886

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER	46	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 310 (US 67)/317 (US 24)
** (87-1)I-1, TS-2

PAY CODES	ITEMS	UNITS	TOTAL	Resurfacing RURAL 90% FED 10% STATE I000-1A	Signals RURAL 90% FED 10% STATE Y031-1F	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	18		18	
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	64		64	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	48		48	
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	57		57	
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	120		120	
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	93		93	
81400400	CONCRETE HANDHOLE	EACH	3		3	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	129		129	
81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	1,112		1,112	
82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	2		2	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	826		826	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,151		1,151	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	313		313	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,416		1,416	
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	313		313	
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	197		197	
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 6 PAIR	FOOT	749		749	
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	3		3	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP 310 (US 67)/317 (US 24)
SECTION (87-1)I-1, TS-2
SCHUYLER COUNTY

SCALE: VERT. : NONE HORIZ.
DATE : MARCH 2005

DRAWN BY
CHECKED BY

PLOT DATE = 4/7/2005
FILE NAME = c:\projects\d652104\shtsoq.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = baxj