

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
502		ADAMS	315	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* (53RS-7, P(RS-2))N, TS
CONTRACT NO. 72897

SUMMARY OF QUANTITIES					
PAY CODE	PAY ITEM	UNITS	TOTAL QUANTITY	J000 - 1A 100 % State QUANTITY	Y031-1F 100 % State QUANTITY
20029302	Grout Repair	L sum	1	1	
20048665	Railroad Protective Liability Insurance	L sum	1	1	
550A0050	Storm Sewers, Class A, Type 1 - 12"	foot	111	111	
550A0090	Storm Sewers, Class A, Type 1 - 18"	foot	55	55	
550A0340	Storm Sewers, Class A, Type 2 - 12"	foot	254	254	
550A0380	Storm Sewers, Class A, Type 2 - 18"	foot	579	579	
550A0410	Storm Sewers, Class A, Type 2 - 24"	foot	203	203	
20200100	Earth Excavation	cu yd	11109	11109	
20800150	Trench Backfill	cu yd	925	925	
25000210	Seeding, Class 2A	acre	1.34	1.34	
25000400	Nitrogen Fertilizer Nutrient	pound	121	121	
25000500	Phosphorous Fertilizer Nutrient	pound	121	121	
25000600	Potassium Fertilizer Nutrient	pound	121	121	
28000250	TEMPORARY EROSION CONTROL SEEDING	pound	96	96	
25100115	Mulch, Method 2	acre	1.34	1.34	
28000300	Temporary Ditch Checks	each	13	13	
28000400	Perimeter Erosion Barrier	foot	7074	7074	
28100125	Stone Riprap, Class B3	sq yd	61	61	
28200100	Filter Fabric for use with Riprap	sq yd	61	61	
31101810	Sub-base Granular Material, Type B 12"	sq yd	17898	17898	
31102100	Sub-base Granular Material, Type C 4"	sq yd	2235	2235	
31200100	Stabilized Sub-base 4"	sq yd	15663	15663	
40600200	Bituminous Materials (Prime coat)	tons	0.4	0.4	
40600300	Aggregate (Prime Coat)	tons	2	2	
42000501	Portland Cement Concrete Pavement 10" (Jointed)	sq yd	14275	14275	
42300400	Portland Cement Concrete Driveway Pavement, 8 Inch	sq yd	830	830	
44000100	Pavement Removal	sq yd	7485	7485	
44000200	Driveway Pavement Removal	sq yd	1325	1325	
44000400	Gutter Removal	foot	2824	2824	
44001430	Bituminous Shoulder Removal	sq yd	1024	1024	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 502 (IL 57) & RADIO ROAD
 SECTION (53RS-7, P(RS-2)) N, TS
 ADAMS COUNTY
 QUINCY, IL
 SCALE: VERT. DRAWN BY TMJ
 HORIZ. CHECKED BY MEB
 DATE 01-23-04

ct:\projects\d653004\cover.dgn
 2/16/2005
 *REF01