USERNAME_
5/6/2005
c:\projects\74049d\d03004pa.dgn
SCH

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	(1Z,17Z)RS-2	CRAWFORD	14	5
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 74049

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	AVERAGE PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "D", N90	BITUMINOUS SURFACE REMOVAL, 1 1/2"	TEMPORARY RAMP
	FOOT	FOOT	SQ YD	GALLON	TON	TON	SQ YD	SQ YD
1164+40.00 TO 1166+35.00	195.0	40.0	866.7	86.7	1.7	72.8	866.7	22.2
1166+35.00 TO 1170+90.00	455.0	45.5	2300.3	230.0	4.6	193.2	2300.3	
1170+90.00 TO 1173+15.00	225.0	51.0	1275.0	127.5	2.6	107.1	1275.0	
1173+15.00 TO 1175+15.00	200.0	57.0	1266.7	126.7	2.5	106.4	1266.7	
1175+15.00 TO 1175+82.00	67.0	63.0	469.0	46.9	0.9	39.4	469.0	
1175+82.00 TO 1176+72.00	90.0	57.0	570.0	57.0	1.1	47.9	570.0	
1176+72.00 TO 1180+10.00	338.0	51.0	1915.3	191.5	3.8	160.9	1915.3	
1180+10.00 TO 1183+96.00	386.0	43.5	1865.7	186.6	3.7	156.7	1865.7	
1183+96.00 TO 1191+01.00	705.0	36.0	2820.0	282.0	5.6	236.9	2820.0	
1191+01.00 BK=0+00.00 AH 0+00.00 TO 19+47.00	1947.0	36.0	7788.0	778.8	15.6	654.2	7788.0	17.8
TOTALS	4608.0		21137.0	2114.0	42.0	1776.0	21137.0	40.0



TEMPORARY RAMP DETAIL
STA 1164+40 TO STA 1164+45
STA 19+42 TO STA 19+47

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH
1164+40.00 TO 1170+90.00	650.0	52.8	1625.0				52.8	1625.0				256.0	42.7	32.0
1170+90.00 TO 1173+50.00	260.0	17.6	650.0	65.0			17.6	650.0	65.0			168.0	28.0	17.0
1173+50.00 TO 1175+15.00	165.0		412.5	82.5				412.5	82.5			128.0	21.3	10.0
1175+15.00 TO 1175+80.00	65.0	35.2	162.5	81.3			35.2	162.5	81.3			64.0	10.7	7.0
1175+80.00 TO 1180+10.00	430.0	17.6	1075.0	107.5			17.6	1075.0	107.5			264.0	44.0	27.0
1180+10.00 TO 1183+96.00	386.0	35.2	965.0				35.2	965.0				160.0	26.7	20.0
1183+96.00 TO 1185+55.00	159.0		664.0		62.0			664.0		62.0		64.0	10.7	8.0
1185+55.00 TO 1185+65.00	10.0		20.0					20.0						
1185+65.00 TO 1186+40.00	75.0	17.6	150.0	75.0		25.0	17.6	150.0	75.0		25.0	32.0	5.3	6.0
1186+40.00 TO 1187+37.00	97.0			73.0		11.0			73.0		11.0	32.0	5.3	
1187+37.00 TO 1188+18.00	81.0		364.0		47.0			364.0		47.0		64.0	10.7	12.0
1188+18.00 TO 1188+92.00	74.0	17.6	148.0				17.6	148.0						
1188+92.00 TO 1190+51.00	159.0		397.5					397.5				64.0	10.7	8.0
1190+51.00 TO 1191+01.00	50.0	17.6	125.0				17.6	125.0				16.0	2.7	2.0
1191+01.00 BK=0+00.00 AH 0+00.00 TO 16+71.00	1671.0	123.2	4177.5	86.0			123.2	4177.5	86.0			672.0	112.0	84.0
16+71.00 TO 18+20.00	149.0		627.0		59.0			627.0		59.0		64.0	10.7	8.0
18+20.00 TO 18+30.00	10.0		20.0					20.0						
18+30.00 TO 19+30.00	100.0	17.6	200.0	100.0		23.0	17.6	200.0	100.0		23.0	48.0	8.0	9.0
19+30.00 TO 19+47.00	17.0			70.0					70.0					
TOTALS		352.0	11783.0	740.0	168.0	59.0	352.0	11783.0	740.0	168.0	59.0	2096.0	349.0	248.0

CLASS D PATCHING SCHEDULE

LOCATION	LANE	LENGTH	WIDTH	CLASS D PATCHES, TYPE IV, 10 INCH
		FOOT	FOOT	SQ YD
1188+55	EB	110.0	7.5	91.7
			TOTAL =	92.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

REVISED 5-9-05