ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
789	1T	MADISON	15	3
STA.		TO STA.		

CONTRACT NO.: 76648

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN Y007 100% STATE		
*	20200200	ROCK EXCAVATION	CU YD	44	44		
	21400100	GRADING AND SHAPING DITCHES	FOOT	100	100		
	25000200	SEEDING, CLASS 2	ACRE	0.7	0.7		
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
	28000300	TEMPORARY DITCH CHECKS	EACH	7	7		
	28000500	INLET AND PIPE PROTECTION	EACH	2	2		
	44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	54	54		
	44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	118	118		
	44213200	SAW CUTS	FOOT	115	115		
	48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	54	54		
	50105220	PIPE CULVERT REMOVAL	FOOT	486	486		
	51205200	TEMPORARY SHEET PILING	SQ FT	3400	3400		
	54010808	PRECAST CONCRETE BOX CULVERT 8' X 8'	FOOT	170	170		
	54011008	PRECAST CONCRETE BOX CULVERT 10' X 8'	FOOT	316	316		
	67100100	MOBILIZATION	L SUM	1	1		
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	72	72		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24	24		
	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	112	112		
	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	36	36		
	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	18	18		
	80300100	LOCATING UNDERGROUND CABLE	FOOT	300	300		
	81012600	CONDUIT IN TRENCH, 2" PVC	FOOT	313	313		
*	81400400	CONCRETE HANDHOLE	EACH	1	1		
	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	313	313		
	87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18, 6 PAIR	FOOT	98	98		
	87900200	DRILL EXISTING HANDHOLE	EACH	2	2		
	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	228	228		
	89502380	REMOVE EXISTING HANDHOLE	EACH	1	1		

*SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		

$DATE$
3/30/2005
c:\oracle\pwrs\wa029823\plan\h897a.dgn
$REF-
$REF-

PLOT DATE: 3/30/2005