

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-RS-1, 82-RB-1, 21	ST. CLAIR	89	3
STA. TO STA.				
CONTRACT NO.: 76813				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-64 MAINLINE	GREENMOUNT RD	S. LINCOLN AVE	N. MAIN STREET	IL RTE 158 (SB)	IL RTE 158 (NB)
				I000	SN 082-0344 SFTY-2A	(FAS 843) SN 082-0181 X771-2A	(FAS 844) SN 082-0182 X771-2A	(FAP 674) SN 082-0183 SFTY-2A	(FAP 674) SN 082-0184 SFTY-2A
20200100	EARTH EXCAVATION	CU YD	93			45	48		
20400800	FURNISHED EXCAVATION	CU YD	569	569					
25000200	SEEDING, CLASS 2	ACRE	0.5	0.5					
25100115	MULCH, METHOD 2	ACRE	0.5	0.5					
28100201	STONE RIPRAP, CLASS A1	TON	291			59	64	84	84
28100205	STONE RIPRAP, CLASS A3	TON	258			52	58	74	74
28200100	FILTER FABRIC	SQ YD	1038			208	230	300	300
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	65	65					
40600300	AGGREGATE (PRIME COAT)	TON	311.5	311.5					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13.1	13.1					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2014	2014					
40600990	TEMPORARY RAMP	SQ YD	308.2	308.2					
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	108.3	108.3					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	578	578					
44004250	PAVED SHOULDER REMOVAL	SQ YD	335			163	172		
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	247	247					
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	185	185					
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	750	750					
44213000	PATCHING REINFORCEMENT	SQ YD	1181	1181					
44213200	SAW CUTS	FOOT	4660	4660					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1873	1873					
45100100	CRACK ROUTING (PAVEMENT)	FOOT	220					110	110
45100200	CRACK FILLING	POUND	3185	3185				100	100
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2750	2750					
48202090	BITUMINOUS SHOULDERS SUPERPAVE 2 1/2"	SQ YD	14009.1	14009.1					
48202115	BITUMINOUS SHOULDERS SUPERPAVE 3 3/4"	SQ YD	71721.7	71721.7					
50104000	BRIDGE RAIL REMOVAL	FOOT	1987			474	497	508	508
50300100	FLOOR DRAINS	EACH	14			6	8		
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	210					105	105
50300225	CONCRETE STRUCTURES	CU YD	8.2			3.9	4.3		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	44.3			10.6	11.1	11.3	11.3
50300260	BRIDGE DECK GROOVING	SQ YD	2364			1157	1207		
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24			12	12		
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	66			12	11	43	

DATE-TIME
DATE-TIME
DATE-TIME
DATE-TIME