

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-TR-1, 82-TR-1, 21	ST. CLAIR	89	5
STA. TO STA.				
CONTRACT NO.: 76813				

SUMMARY OF QUANTITIES			URBAN 90% FED / 10% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-64 MAINLINE I000	GREENMOUNT RD SN 082-0344 SFTY-2A	S. LINCOLN AVE (FAS 843) SN 082-0181 X771-2A	N. MAIN STREET (FAS 844) SN 082-0182 X771-2A	IL RTE 158 (SB) (FAP 674) SN 082-0183 SFTY-2A	IL RTE 158 (NB) (FAP 674) SN 082-0184 SFTY-2A
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2			1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	33,646	33,646					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	231,412	231,412					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	22,956	22,956					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2464	2464					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	115706	115706					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	22,773	22,773					
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1638			970	668		
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1366			1028	338		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1138	1134		4			
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4			4			
*78200405	GUARDRAIL MARKERS	EACH	56	8		16	16	8	8
*78200520	BARRIER WALL MARKERS, TYPE B	EACH	16			8	8		
*78200530	BARRIER WALL MARKERS, TYPE C	EACH	16			8	8		
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	17	5		4	4	2	2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	492			353	139		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	638	630		8			
X0320887	POLYMER CONCRETE	CU FT	30			15	15		
X0322379	CONCRETE SEALER	SQ YD	5692		2262			1715	1715
X0322729	MATERIAL TRANSFER DEVICE	TON	27,770	27,770					
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	192			95	97		
X0301424	SILICONE JOINT SEALER	FOOT	149			49	100		
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	28			14	14		
X4066570	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N80	TON	11736	11736					
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	337			164	173		
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	13,555	13,555					
X4066920	POLYMERIZED LEVELING BINDER (MACHINE METHOD) SUPERPAVE N105	TON	2,479	2,479					
X4421000	PARTIAL DEPTH PATCHING	TON	209.7	209.7					
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	1872.2	1872.2					
*XX004684	REPAIR AND REPLACE DAMAGED CONDUIT	FOOT	2					1	1
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	2480			1214	1266		

DATE-TIME
CON-SPEC
REF

* SPECIALTY ITEMS

PLOT DATE: DATE-TIME

Rev.