

FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-7RS-1, 82-7HB-1, 2I	ST. CLAIR	89	8
STA.		TO STA.		
CONTRACT NO.: 76813				

RESURFACING SCHEDULE																
STATION	STATION	LENGTH	LANE WIDTH	TOTAL LANES	TOTAL WIDTH	AREA	BINDER 2 1/4"	LEVEL BINDER 1"	BIT SURFACE 1 1/2"	BIT (PRIME)	AGG. (PRIME)	BIT. SHLDRS. - RESURFACING - 3 3/4"		BIT. SHLDRS. - RESURFACING - 2 1/2"		AGG. SHLDRS. TYPE - B
		(FT)	(FT)		(FT)	SQ. YD.	TON	TON	TON	TON	TON	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TONS
MAINLINE																
744+30	744+40	10.0	12	4	48	53.33	6.7		5.2	0.0	0.1	13.3	22.2			1.0
744+40	759+62.08	1522.1	12	4	48	8117.76	1022.8		681.9	3.4	16.2	2029.4	3382.4			157.8
759+62.23	816+85.58	5723.4	12	4	48	30524.53	3846.1		2584.1	12.7	61.0	7631.1	12718.6			593.5
816+85.16	859+63.7	4278.5	12	4	48	22818.88	2875.2		1918.8	9.5	45.6	5704.7	9507.9			443.7
859+77.63	912+26.1	5248.5	12	4	48	27991.84	3527.0		2351.3	11.7	58.0	6998.0	11663.3			544.3
914+25.72	948+05	3379.3	12	4	48	18022.83	2270.9		1513.9	7.5	36.0	4505.7	7509.5			350.4
948+05	948+15	10.0	12	4	48	53.33	6.0		4.5	0.0	0.1	13.3	22.2			1.0
SUBTOTAL																
2091.8																
10% EXIST. LOW AGG. SHLDR																
2300.9																
RAMPS @ GM																
S.W.		1002.6	16	1	16	1782.40		224.6	149.7	1.1	5.3					
N.W.		481.9	16	1	16	856.71		107.9	72.0	0.5	2.6					
S.E.		1085.8	16	1	16	1930.31		243.2	162.1	1.2	5.8					
N.E.		410.3	16	1	16	729.42		91.9	61.3	0.5	2.2					
RAMPS @ W.S.																
S.W.		771.8	16	1	16	1372.09		172.9	115.3	0.9	4.1					
S.E.		1711.5	16	1	16	3042.67		383.4	256.6	1.9	9.1					
RAMPS @ 158																
RAMP A		1858.6	16	1	16	3304.18		185.0	277.6	2.1	9.9		826.0	1239.1		66.3
RAMP B		1214.8	16	1	16	2159.64		120.9	181.4	1.4	6.5		539.9	809.9		43.3
RAMP C		1962.9	16	1	16	3489.60		195.4	293.1	2.2	10.5		872.4	1308.6		70.0
RAMP D		1270.1	16	1	16	2257.96		126.4	189.7	1.4	6.8		564.5	848.7		45.3
RAMP E		1885.5	16	1	16	3352.00		187.7	281.6	2.1	10.1		838.0	1257.0		67.2
RAMP F		1225.0	16	1	16	2177.78		122.0	182.9	1.4	6.5		544.4	816.7		43.7
RAMP G		1915.7	16	1	16	3405.89		190.7	286.1	2.1	10.2		851.4	1277.1		68.3
RAMP H		1275.6	16	1	16	2267.73		127.0	190.5	1.4	6.8		566.9	850.4		45.5
SUB TOTAL																
26,895.6																
44,826.0																
5,803.6																
8,405.5																
TOTALS																
							13554.7	2479.1	11,736.4	85.0	311.5	71,721.7	14,009.1			2,750

* LEVEL BINDER THICKNESS ON RAMPS AT IL RTE. 158 SHALL BE 1"
SEE RESURFACING TRANSITION DETAIL ON SHEET 17

GUARDRAIL SCHEDULE								
LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL	TRAFFIC BARRIER TERMINAL TYPE 1 (SPL) TANGENT	TRAFFIC BARRIER TERMINAL TYPE 1 (SPL) FLARED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6B	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS
	FT	FT	EACH	EACH	EACH	EACH		
I-64 MAINLINE								
STATION	STATION							
815+65	817+15	137.5		1	1		1	4
816+55	818+05	137.5		1	1		1	4
882+27.5	882+90	50		1			1	
911+63	912+13	50		1			1	
914+39	914+89	50		1			1	
S. LINCOLN ST. - SN 082-0181								
NE QUAD	162.5	100	1			1	1	4
SE QUAD	200	162.5	1			1	1	4
NW QUAD	162.5	100	1			1	1	4
SW QUAD	200	100	1			1	1	4
N. MAIN ST. - SN 082-0182								
NE QUAD	225	112.5	1			1	1	4
SE QUAD	225	175	1			1	1	4
NW QUAD	225	175	1			1	1	4
SW QUAD	225	112.5	1			1	1	4
IL 158 SOUTHBOUND - SN 082-0183								
NE QUAD	187.5	200		1		1	1	4
NW QUAD	162.5	125	1			1	1	4
IL 158 NORTHBOUND - SN 082-0184								
SE QUAD	187.5	200	1			1	1	4
SW QUAD	162.5	125		1		1	1	4
TOTALS	2750	1875	10	7	2	12	17	56

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
MISCELLANEOUS SCHEDULES
 FAI 64
 SECTION 82-7RS-1, 82-7HB-1, 2I
 ST. CLAIR COUNTY
 DRAWN BY:

PLOT DATE: 4/26/2005

DATE: 4/26/2005
 REF: 082-0181-0184
 REF: 082-0181-0184