F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	11
STA. 10+70.70	TO STA. 66+16.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83781

PLAN
SURVEYED
PLOTTED
ALL OF WAY CHECKED
NOTE BOOK
NO.
CADD FILE NAME
BY
DATE

PROFILE
SURVEYED
PLOTTED
ALL OF WAY CHECKED
BAL. NOTED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.
BY
DATE

STATION	DISTANCE	20200100 EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (REDUCED FOR SHRINKAGE 0.15%)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EMBANKMENT	20400800 FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (–)	20700220 POROUS GRANULAR EMBAMKMENT, SUBGRADE	66900200 NONSPECIAL WASTE DISPOSAL
	FT	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
35+00.00	54.6	72.1	61.3	17.7	14.2	47.1	41.6	51.5
35+08.50	8.5	10.5	8.9	3.0	3.3	5.6	6.5	11.1
35+50.00	41.5	49.2	41.8	15.9	18.1	23.7	31.6	54.3
35+56.96	7.0	7.2	6.1	2.7	4.3	1.8	5.3	9.0
36+00.00	43.0	33.0	28.0	13.1	39.4	-11.4	32.8	46.6
36+54.25	54.3	27.2	23.2	14.6	33.6	-10.5	107.9	87.0
36+68.40	14.2	7.3	6.2	4.4	0.8	5.4	45.5	32.0
36+82.90	14.5	15.3	13.0	9.0	0.7	12.3	46.7	27.6
37+00.00	17.1	23.4	19.9	14.4	1.7	18.1	45.4	27.0
37+50.00	50.0	39.3	33.4	25.8	9.8	23.6	101.4	86.7
37+79.34	29.3	10.6	9.0	7.3	3.4	5.6	57.3	56.5
38+00.00	20.7	8.0	6.8	5.0	0.5	6.3	39.8	41.2
38+04.83	4.8	2.1	1.8	1.2	0.0	1.8	9.2	9.9
38+50.00	45.2	15.1	12.8	10.5	5.2	7.6	85.2	103.6
39+00.00	50.0	10.7	9.1	20.9	10.0	-0.9	91.8	127.6
39+50.00	50.0	12.6	10.8	25.7	5.1	5.7	81.5	115.7
40+00.00	50.0	13.4	11.4	10.4	7.9	3.5	36.3	65.7
40+46.99	47.0	22.1	18.8	0.0	7.9	10.9	0.0	28.3
40+50.00	3.0	1.4	1.2	0.0	0.2	1.0	0.0	1.9
40+72.25	22.3	6.7	5.7	0.0	1.2	4.5	0.0	13.3
41+00.00	27.8	7.8	6.6	0.0	3.9	2.7	0.0	14.1
41+50.00	50.0	10.9	9.2	0.0	12.6	-3.4	0.0	27.1
42+00.00	50.0	11.7	9.9	0.0	12.7	-2.8	0.0	39.7
42+50.00	50.0	11.2	9.5	3.7	12.8	-3.3	18.1	74.5
42+64.03	14.0	4.0	3.4	1.8	2.1	1.3	10.2	28.0
43+00.00	36.0	11.0	9.3	4.4	7.2	2.1	33.4	80.4
43+17.22	17.2	2.3	2.0	1.2	3.4	-1.4	23.1	46.9
43+50.00	32.8	2.3	1.9	0.3	10.0	-8.0	34.2	66.5
43+72.82	22.8	6.5	5.6	0.8	10.2	-4.7	12.3	24.8
43+96.27	23.5	11.1	9.4	1.2	7.4	2.1	12.7	26.5
44+00.00	3.7	1.9	1.6	0.2	1.3	0.3	2.0	4.3
44+50.00	50.0	28.8	24.5	2.8	13.0	11.5	27.0	53.5
44+62.39	12.4	7.4	6.3	0.7	1.7	4.6	6.7	10.3
45+00.00	37.6	15.3	13.0	2.2	18.1	-5.1	20.3	12.7
45+21.70	21.7	4.4	3.8	1.2	14.7	-10.9	11.7	0.0
45+50.00	28.3	4.8	4.1	1.5	18.7	-14.6	15.3	0.0
45+81.62	31.6	5.9	5.0	0.8	21.6	-16.6	8.5	0.0
46+00.00	18.4	4.2	3.6	0.0	9.7	-6.1	0.0	0.0
46+32.34	32.3	9.4	8.0	0.0	9.6	-1.6	0.0	9.0
46+50.00	17.7	5.4	4.6	0.0	5.9	-1.3	0.0	14.1
46+68.14	18.1	6.6	5.6	0.0	10.4	-4.8	0.0	22.0
46+87.74	19.6	13.6	11.5	0.0	6.8	4.8	0.0	28.4

STATION	DISTANCE	20200100 EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (REDUCED FOR SHRINKAGE 0.15%)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EMBANKMENT	20400800 FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (–)	20700220 POROUS GRANULAR EMBAMKMENT, SUBGRADE	66900200 NONSPECIAL WASTE DISPOSAL
	FT	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
47+00.00	12.3	10.7	9.1	0.0	1.1	8.0	0.0	18.4
47+27.70	27.7	22.1	18.8	0.0	2.2	16.6	0.0	33.0
47+50.00	22.3	14.5	12.3	0.0	5.7	6.6	0.0	12.6
47+85.51	35.5	15.3	13.0	0.0	14.7	-1.7	0.0	4.0
48+00.00	14.5	5.7	4.8	0.0	6.6	-1.8	0.0	0.0
48+44.52	44.5	13.4	11.4	0.0	20.9	-9.5	0.0	0.0
48+50.00	5.5	1.1	0.9	0.0	2.1	-1.1	0.0	0.0
49+00.00	50.0	21.0	17.9	6.6	8.8	9.0	28.1	27.6
49+07.17	7.2	5.2	4.4	2.1	0.1	4.3	8.1	8.5
49+50.00	42.8	32.7	27.8	32.0	7.0	20.9	50.0	56.8
49+67.00	17.0	16.0	13.6	20.4	6.0	7.6	20.6	23.0
49+84.26	17.3	25.5	21.7	21.5	3.3	18.4	21.7	22.7
49+92.88	8.6	13.7	11.7	10.7	0.7	11.0	11.0	11.2
50+00.00	7.1	8.9	7.5	8.6	1.0	6.5	9.0	9.3
50+50.00	50.0	51.3	43.6	48.4	7.1	36.5	66.7	68.4
51+00.00	50.0	104.0	88.4	67.7	6.1	82.2	99.3	57.3
51+50.00	50.0	86.4	73.5	51.2	7.0	66.4	102.6	64.1
51+99.11	49.1	6.5	5.5	1.8	4.7	0.8	37.5	41.6
52+30.22	31.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0
52+50.00	100.0	14.8	12.5	4.8	6.3	6.3	76.3	81.6
53+00.00	50.0	14.9	12.6	5.0	5.2	7.5	76.3	89.4
53+11.86	161.9	95.9	81.5	24.0	10.4	71.1	246.9	329.5
53+50.00	38.1	23.9	20.3	19.6	1.2	19.1	58.2	81.2
54+00.00	50.0	40.6	34.5	56.0	0.8	33.8	80.9	111.1
54+32.45	32.4	23.3	19.8	57.6	0.2	19.6	68.9	99.1
54+50.00	17.6	17.2	14.6	32.1	0.0	14.6	36.5	47.5
54+84.57	34.6	46.4	39.4	47.4	0.0	39.4	50.9	54.8
55+00.00	15.4	11.9	10.1	18.4	0.4	9.7	20.2	24.1
55+50.00	50.0	33.9	28.8	45.0	1.4	27.4	63.2	77.7
55+56.68	6.7	4.7	4.0	3.9	0.1	3.9	8.2	10.3
56+00.00	43.3	21.3	18.1	15.0	6.7	11.4	51.4	60.9
56+35.31	35.3	13.1	11.1	5.7	7.5	3.6	39.8	48.3
56+50.00	14.7	6.1	5.2	2.8	1.5	3.6	16.0	21.6
56+57.99	8.0	3.0	2.6	1.9	0.5	2.1	8.6	11.9
56+91.92	33.9	13.6	11.6	13.1	1.8	9.8	36.7	50.6

Stanley Consultants INC.
8501 West Higgins Road
Suite 730
Chicago, Illinois 60631-2801 Illinois Firm Registration No.: 184-000633

REVISIONS NAME	DATE

VILLAGE OF VILLA PARK, ILLINOIS

SOUTH VILLA AVENUE SCHEDULE OF QUANTITIES SHEET 2 OF 4

SCALE: NONE
DRAWN BY: E.D.
DATE: 11-NOV-2004
CHECKED BY: J.T.G.

O:\15367\Phase2\07-Design\05-Dwgs\sht\367soq01.dgn
11-NOV-2004