F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	54
STA. 10+70.70	TO STA. 66+16.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83781

PLAN / PROFILE — BY — DATE
SURVEYED
PLOTTED
ALIGNMENT CHECKED
GRADES CHECKED
CADD FILE NAME
NOTE BOOK
NO.
STRUCTURE NOTATNS CHKD

PIPE TABLE

PIPE NO.	STATION	–	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)
1	11+00.00		11+00.00	CL A TY 2	12	24.0	6.67
2	11+00.00		11+00.00	CL A TY 2	12	12.0	3.34
4	11+50.00		11+60.48	CL A TY 2	12	10.5	2.92
5	11+50.00		11+60.48	SS (WM REQ)	12	10.5	2.70
6	11+60.48		11+60.48	CL A TY 2	12	12.0	3.71
7	11+60.48		11+60.48	CL A TY 2	12	24.0	7.18
9	12+20.00		12+20.00	CL A TY 2	12	24.0	6.67
10	12+65.00		12+65.00	CL A TY 2	12	12.0	3.34
11	12+65.00		12+65.00	CL A TY 2	12	24.0	6.67
12	13+35.00		13+35.00	CL A TY 2	12	12.0	4.60
13	13+35.00		13+35.00	SS (WM REQ)	12	24.0	6.67
14	14+75.00		14+25.00	CL A TY 2	12	52.3	19.48
15	14+25.00		14+25.00	SS (WM REQ)	12	24.0	6.67
16	15+50.00		15+50.00	CL A TY 1	12	27.6	6.21
17	14+00.00		14+25.00	SS (WM REQ)	12	31.6	10.11
18	14+25.00		14+25.00	CL A TY 2	12	12.0	3.34
19	15+50.00		15+50.00	SS (WM REQ)	12	42.4	9.54
21	13+60.83		13+35.00	SS (WM REQ)	12	33.5	22.24
24	11+00.00		10+75.00	CL A TY 2	38x60	28.5	21.20
26	11+60.48		11+00.00	CL A TY 2	38x60	60.0	38.70
28	12+20.00		11+60.48	CL A TY 2	34x53	60.0	37.92
30	12+65.00		12+20.00	CL A TY 2	34x53	45.0	33.93
32	13+35.00		12+65.00	CL A TY 2	36	70.0	60.59
34	14+25.00		13+35.00	CL A TY 2	36	90.0	120.14
36	15+50.00		14+25.00	CL A TY 2	12	125.0	32.13
38	11+60.48		11+60.48	CL A TY 2	12	19.1	12.07
40	12+65.00		12+65.00	CL A TY 1	12	19.8	6.34
41	17+70.00		17+70.00	CL A TY 2	12	18.0	4.82
42	10+75.00		10+52.68	CL A TY 2	15	25.5	19.44
43	18+75.00		18+75.00	CL A TY 2	12	18.0	6.52
44	18+75.00		18+75.00	CL A TY 2	12	6.0	2.17
45	19+80.00		19+80.00	CL A TY 2	12	18.0	5.00
46	19+80.00		19+80.00	CL A TY 2	12	6.0	1.61
47	20+90.00		20+90.00	CL A TY 2	12	18.0	13.11
48	20+90.00		20+90.00	CL A TY 2	12	6.0	2.05
49	21+70.00		21+70.00	CL A TY 2	12	18.0	4.82
50	21+70.00		21+70.00	CL A TY 2	12	6.0	1.92
51	20+90.00		20+90.00	CL A TY 2	12	21.1	16.38
52	17+70.00		17+70.00	CL A TY 2	12	6.0	3.79
53	22+10.00		22+10.00	CL A TY 2	12	18.0	4.82

PIPE TABLE

PIPE NO.	STATION	–	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)
54	17+70.00		17+70.00	CL A TY 2	12	23.1	17.19
56	19+80.00		19+80.00	CL A TY 2	12	21.6	14.00
57	22+90.00		22+75.00	CL A TY 2	12	14.5	4.94
58	24+00.00		24+00.00	CL A TY 2	12	6.0	1.61
59	22+75.00		22+75.00	CL A TY 2	12	18.0	5.00
60	24+78.70		24+78.70	CL A TY 2	12	6.0	1.61
62	25+50.00		25+50.00	CL A TY 2	12	26.7	9.10
64	22+50.00		22+55.00	CL A TY 2	12	6.0	2.05
65	24+00.00		24+00.00	CL A TY 2	12	19.7	5.89
66	21+80.00		21+70.00	SS (WM REQ)	12	25.7	17.48
67	23+81.05		24+00.00	CL A TY 2	12	19.0	12.31
68	22+75.00		22+75.00	CL A TY 2	12	12.0	2.70
69	24+78.70		24+78.70	CL A TY 2	12	18.0	4.43
70	18+75.00		18+75.00	CL A TY 2	12	22.4	15.95
71	24+78.70		24+78.70	CL A TY 2	12	9.8	3.65
72	20+90.00		20+90.00	SS (WM REQ)	12	22.3	15.52
73	25+50.00		25+50.00	CL A TY 2	12	18.0	5.00
75	18+45.00		18+45.00	SS (WM REQ)	12	40.3	29.99
77	20+60.00		20+90.00	CL A TY 2	12	30.0	21.84
80	17+70.00		18+75.00	CL A TY 2	12	105.0	74.77
82	18+75.00		19+80.00	CL A TY 2	12	105.0	73.08
84	19+80.00		20+90.00	CL A TY 2	34x53	110.0	228.10
86	20+90.00		21+70.00	CL A TY 2	34x53	80.0	86.00
88	21+70.00		22+75.00	CL A TY 2	34x53	105.0	67.04
90	22+75.00		23+00.00	CL A TY 2	29x45	25.0	108.88
94	24+00.00		23+00.00	CL A TY 2	29x45	100.0	73.50
96	24+78.70		24+00.00	CL A TY 2	38x60	78.7	89.72
98	25+50.00		24+78.70	CL A TY 2	38x60	71.3	116.65
100	23+00.00		23+00.00	CL A TY 2	29x45	12.0	4.69
102	23+00.00		23+04.15	CL A TY 2	29x45	200.0	35.70
105	29+50.00		29+30.00	CL A TY 2	12	25.6	18.23
107	30+85.00		30+85.00	CL A TY 2	12	24.3	17.69
109	32+00.00		32+00.00	CL A TY 2	12	23.5	8.26
111	27+50.00		27+50.00	CL A TY 2	12	6.0	1.61
112	27+50.00		27+50.00	CL A TY 2	12	18.0	4.82
113	28+25.00		28+25.00	CL A TY 2	12	23.7	16.50
114	29+30.00		29+30.00	CL A TY 2	12	18.0	4.82
115	29+30.00		29+30.00	CL A TY 2	12	6.0	2.24
116	30+35.00		30+35.00	CL A TY 2	12	18.0	5.19
117	30+85.00		30+85.00	CL A TY 2	12	6.0	3.05

PIPE TABLE

PIPE NO.	STATION	–	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)
118	30+65.00		30+85.00	CL A TY 2	12	60.0	49.46
119	31+55.00		31+55.00	CL A TY 2	12	6.0	1.61
120	30+42.80		30+53.00	SS (WM REQ)	12	40.3	27.40
121	32+00.00		32+15.03	CL A TY 2	12	15.0	5.75
122	30+53.00		30+65.00	SS (WM REQ)	12	12.0	7.58
123	32+15.03		32+15.03	CL A TY 2	12	7.3	2.18
124	30+90.30		30+77.00	CL A TY 2	12	41.2	26.04
125	34+25.00		34+25.00	CL A TY 2	12	12.0	9.32
126	30+77.00		30+65.00	CL A TY 2	12	12.0	8.54
127	35+35.00		35+35.00	CL A TY 2	12	12.0	3.34
128	31+55.00		31+55.00	CL A TY 2	12	18.0	4.82
129	33+00.00		33+00.00	CL A TY 2	12	30.3	30.82
130	32+15.03		32+15.03	CL A TY 2	12	19.4	14.67
131	36+30.00		36+30.00	CL A TY 2	15	17.6	5.34
132	34+25.00		34+25.00	CL A TY 2	12	24.0	15.94
133	37+00.00		37+00.00	SS (WM REQ)	12	25.8	8.26
134	35+35.00		35+35.00	CL A TY 2	12	24.0	6.92
135	34+25.00		34+25.00	CL A TY 2	12	12.2	8.88
136	35+90.00		35+90.00	CL A TY 2	12	24.0	21.70
137	36+00.00		36+30.00	CL A TY 2	12	33.0	11.60
138	36+30.00		36+30.00	CL A TY 2	12	24.0	6.67
140	36+46.57		36+30.00	CL A TY 2	12	16.5	5.63
142	39+04.74		39+04.74	CL A TY 2	12	19.0	3.87
144	39+30.00		39+04.74	CL A TY 2	12	25.2	7.01
146	39+75.00		39+75.00	CL A TY 2	12	18.0	5.00
148	40+30.00		40+30.00	CL A TY 2	12	18.0	4.05
150	41+15.00		40+30.00	CL A TY 2	12	18.0	4.82
152	32+50.00		32+15.03	SS (WM REQ)	12	42.0	33.28
161	38+28.75		38+28.75	CL A TY 2	12	16.2	4.67
163	39+04.74		39+04.74	CL A TY 2	12	16.1	3.44
165	39+30.00		39+04.74	CL A TY 2	12	25.2	7.01
167	40+30.00		40+30.00	CL A TY 2	12	16.0	4.62
169	41+15.00		41+15.00	CL A TY 2	12	16.0	4.45
171	27+50.00		29+30.00	CL A TY 2	12	180.0	122.40
173	29+30.00		30+85.00	CL A TY 2	12	155.6	54.48
175	30+85.00		31+55.00	CL A TY 2	18	70.0	69.51
177	31+55.00		32+15.03	CL A TY 2	38x60	60.0	119.94
179	32+15.03		34+25.00	CL A TY 2	38x60	210.0	378.21
181	34+25.00		35+35.00	CL A TY 2	38x60	110.0	132.66
183	35+35.00		36+30.00	CL A TY 2	38x60	95.0	64.41

REVISIONS NAME	DATE

Stanley Consultants INC.
850 West Higgins Road
Suite 730
Chicago, Illinois 60631-2801 Illinois Firm Registration No.: 184-001533

VILLAGE OF VILLA PARK, ILLINOIS

PIPE TABLE
SOUTH VILLA AVENUE
SHEET 1 OF 2

SCALE: NONE
DRAWN BY: E.D.
DATE: 11-NOV-2004
CHECKED BY: J.T.G.

Q:\15367\Phase2\07-Design\05-Dwgs\sht\367cdrsh2.dgn
11-NOV-2004